

51

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
HACKINAC

(County)

Located In:

Corner Code ~~##~~

1. Public Land Survey T ___ R ___
T ___ R ___
T ___ R ___
T ___ R ___
2. Property Controlling S 11 T 44N R 11W 2
in Section S ___ T ___ R ___
3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on July 09, 1992, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| 2 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 |
| 3 | 14 | 15 | 16 | 17 | 18 | 19 | 20 | 21 | 22 | 23 | 24 | 25 | 26 |
| 4 | 27 | 28 | 29 | 30 | 31 | 32 | 33 | 34 | 35 | 36 | 37 | 38 | 39 |
| 5 | 40 | 41 | 42 | 43 | 44 | 45 | 46 | 47 | 48 | 49 | 50 | 51 | 52 |
| 6 | 53 | 54 | 55 | 56 | 57 | 58 | 59 | 60 | 61 | 62 | 63 | 64 | 65 |
| 7 | 66 | 67 | 68 | 69 | 70 | 71 | 72 | 73 | 74 | 75 | 76 | 77 | 78 |
| 8 | 79 | 80 | 81 | 82 | 83 | 84 | 85 | 86 | 87 | 88 | 89 | 90 | 91 |
| 9 | 92 | 93 | 94 | 95 | 96 | 97 | 98 | 99 | 100 | 101 | 102 | 103 | 104 |
| 10 | 105 | 106 | 107 | 108 | 109 | 110 | 111 | 112 | 113 | 114 | 115 | 116 | 117 |
| 11 | 118 | 119 | 120 | 121 | 122 | 123 | 124 | 125 | 126 | 127 | 128 | 129 | 130 |
| 12 | 131 | 132 | 133 | 134 | 135 | 136 | 137 | 138 | 139 | 140 | 141 | 142 | 143 |
| 13 | 144 | 145 | 146 | 147 | 148 | 149 | 150 | 151 | 152 | 153 | 154 | 155 | 156 |

A. Description of original monument and accessories and/or subsequent restoration:

(2) East 1/16 corner between Sections 2 and 11. Corner not established in original survey. Corner established in 1904 and recorded in 1985 by Gerald L. Higgins, RLS. Higgins placed a DNR monument at the corner and marked the following bearing trees: 8" H. Maple S38E 27.3', 10" H. Maple N77W 5.7', 6" H. Maple N45E 16.3', and 8" Ironwood S88E 13.6'. Found no other record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2) Found DNR monument removed from the recorded corner position and the 6" H. Maple and 8" Ironwood bearing trees cut. At the position for the corner, as determined by the two remaining bearing trees, both recovered as recorded, I placed a new DNR monument, described below. I reblazed the top blaze of Higgins' remaining bearing trees and marked two new bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Placed a 1"x32" painted iron pipe capped with a 4" dia. cast aluminum MDNR tablet. Blazed, and scribed, and placed measuring nails in the following new bearing trees:
8" H. Maple S35E, 31.9' (1/16 BT)
4" H. Maple N63E, 31.05' (1/16 BT)
Placed measuring nails in the recorded trees as follows:
10" H. Maple S38E, 27.82'
12" H. Maple N77W, 6.1'



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 8-4-92