

52

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Hackinac

Located In:

Corner Code #

1. Public Land Survey

T 44N R 11W

15

T 44N R 11W

14

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

May 14 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(15) Corner common to Sections 10-11-14-15. Corner monumented in 1972 by Billy D. Buckler, RLS. Corner was monumented with a 3/4" x24" iron buried in E-W road. Witnesses: 24" Hard Maple N12E 79.0', 13" Hard Maple N55W 66.6'.

(14) Quarter corner common to Sections 10-11. Corner reestablished in 1972 by Billy D. Buckler, RLS. Corner marked by a 1" pipe with 4" aluminum cap and the following: 7" Red Pine N76W 92.3', 6" Red Pine S13W 96.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15) Found the 1972 monument, in good condition, at record bearing and distance from the 1972 witnesses. Set measuring nails in and marked new top blazes on the the 1972 witnesses and also marked two new witnesses as described below. Left the monument in place. Corner re-witnessed by T.Stark and D.Lampela, Newberry.

(14) Found the 1972 monument as described, in good condition, and at record bearing and distance from the remaining R. Pine S13W accessory. The other witness was not recovered. The corner monument is buried on the east side of the road, in the shoulder. Marked a new top blaze and set a measuring nail in the remaining 1972 tree and marked three new witnesses as described below. Corner re-witnessed by T.Stark and D.Lampela, Newberry.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Found a 3/4" iron bar, buried. Blazed, scribed, and set measuring nails in the following:

26" H. Maple N12E 79.1' "S11"
15" H. Maple N55W 66.9' "S10"
24" H. Maple N60E 75.25' "S11 NBT"
Twin 12" Maple N35W 16.85' "S10 NBT"
Bearings are magnetic.

(14) Found 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:

10" R. Pine S13W 96.1' "1/4S"
10" R. Pine N54W 77.6' "1/4S NBT"
5" W. Pine N87E 7.2' "1/4S NBT"
10" Spruce N72W 55.25' "1/4S NBT"
Placed a squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 6/25/96

For the Michigan Department of Natural Resources - Forest Management Division