

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey

T 44N R 11W

H4

T R

T R

T R

2. Property Controlling
in Section

S 10 T 44N R 11W

16

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

May 14 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		●		11		12	
5								●					
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(H4) Center of Section 10. Corner not established in the original survey. Found no subsequent record.

(16-Sec. 10) East 1/16 corner between Sections 10-15. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H4) Found no monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/4 corners 2640.20' North, 2650.98' East, 2624.42' South, and 2664.53' West. At the position for the corner, I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed by T.Stark and D.Lampela, Newberry.

(16-Sec. 10) Found no monumentation at the corner position. Established the corner midway and on a straight line between Section and Quarter Section corners 1326.49 feet east and West. At the position for the corner, I placed a 1" IDx36" iron pipe capped with a yellow plastic cap stamped MICH DNR LS 33986, set below the surface in the approximate centerline of an E-W road. Corner placed by T.Stark and D. Lampela, Newberry.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H4) Set 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails
in the following:

8" Balsam S87W 17.9' "CS BT"
14" Cedar N40W 25.35' "CS BT"
5" W. Birch S30E 37.4' "CS BT"
5" Spruce S02W 19.9' "CS BT"

Placed a squared and scribed cedar post
adjacent. Bearings are magnetic.

(16) Set 1" pipe with plastic cap.
Blazed, scribed, and set measuring nails
in the following:

10" Y. Birch N27W 40.20'
26" H. Maple N07W 37.80'
5" Elm N48E 37.75'
Cor. fence post S67W 53.35' (no blazes)

Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Surveyor's Michigan License No. 33986

Date

6/25/96

For the Michigan Department of Natural Resources - Forest Management Division