

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located in:

Corner Code #

1. Public Land Survey	T	44NR	11W	12
	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S	2	T 44NR 11W	12
	S	T	R	
3. Miscellaneous Property in Sec.	S	T	R	
	S	T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

12 Sep 29 1998
 12 Sep 30 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:


(12) Quarter corner common to Sections 2-3. According to the first transcription of the original GLO notes, the corner was established in 1849 by William Ives as follows: "South corrected...38.40 Set qr. section post. Cedar 7 East 13, do 10 S80W 15... 78.44 Section corner". The GLO plat approved Feb. 13, 1850 by Charles Noble, Surveyor General show regular measurements along the West line of Section 2 with the only fractional measurement being 18.44 ch. on the west side of the government lot.
 (12-Sec. 2) South 1/16 corner, Section 2. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(12) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner 40 chains, proportionate to the original plat record, 2626.53' north of the Section corner common to 2-3-10-11, on a line of mean true bearing between that corner and the corner common to 2-3 T44N-R11W and 34-35 T45N-R11W which is 2524.09' North. At the position for the corner I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and M.Feldpausch, Newberry District Office.
 (12-Sec. 2) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Center of Section 1312.48' North and Quarter corner 1312.48' South. At the position for the corner I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 10" Cedar S27E 14.45' "1/4S NBT" 8" Cedar N46E 19.55' "1/4S NBT" 6" Cedar S02E 4.15' "1/4S NBT" 6" Cedar N82W 15.25' "1/4S NBT" Placed a 4" squared and scribed cedar post adjacent. Bearings are magnetic.	(12) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 8" Ironwood N42E 7.95' "S1/16 BT" 10" Ironwood N30W 6.85' "S1/16 BT" 14" Maple S54W 20.15' "S1/16 BT" 14" Maple S09W 21.65' "S1/16 BT" Placed squared and scribed cedar post adjacent. Placed location poster on 6" maple Approx. 210' East on N-S trail. Bearings are magnetic.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/28/98

For the Michigan Department of Natural Resources - Forest Management Division