

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S 2 T 44 R 11 8

S 2 T 44 R 11 11

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

Oct 01 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(8-Sec. 2) West 1/16 corner, Section 2. Corner not established in the original survey. Found no subsequent record.

(11-Sec. 2) Southwest 1/16 corner of Section 2. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(8-Sec. 2) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1321.12' West and Center of Section 1321.12' East. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped and buried it below the surface in the SW side of an intersection of trails north, south, and east. Corner placed and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

(11-Sec. 2) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners 1324.23' West, 1323.85' East, 1312.87' North, and 1313.32' South. At the position for the corner I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(8) Set 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails
in the following:

14" Maple N81E 28.1' "N1/16 BT"
12" Maple S15E 23.05' "N1/16 BT"
24" Twin Maple S40W 16.0' "N1/16 BT"
10" Maple N28E 23.2' "N1/16 BT"

Placed location poster on cedar post
approx 9' west. Bearings are magnetic.

(11) Set 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails
in the following:

8" Maple N05E 8.75' "SW1/16 BT"
8" Maple NS2E 8.2' "SW1/16 BT"
6" Maple S54E 5.15' "SW1/16 BT"
4" Maple N18W 10.45' "SW1/16 BT"

Placed a 3" squared and scribed cedar
post adjacent.



Signed by Stephan J. Szyszkoski

Date 12/28/98

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division