

152

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>2</u> T <u>44N</u> R <u>11W</u>	<u>4</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Oct 01 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 2) Northwest 1/16 corner Section 2. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 2) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a yellow plastic cap stamped "MICH DNR PS 33986". Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office. The monument was buried at the corner position, which falls on the east side of a N-S trail.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set 1" pipe with yellow plastic cap. Blazed, scribed, and set measuring nails in the following:

24' Trip. Maple N40E 20.75' "NW1/16 8T"  
14' Maple N62E 9.65' "NW1/16 8T"  
8' Maple S59E 12.4' "NW1/16 8T"  
8' Hemlock S65W 22.6' "NW1/16 8T"

Placed a location poster on a cedar post approx. 11.5' west. Bearings are magnetic.



Signed by \_\_\_\_\_

*Stephan J. Szyszkoski*

Date \_\_\_\_\_

12/28/98

Surveyor's Michigan License No. \_\_\_\_\_

33986

For the Michigan Department of Natural Resources - Forest Management Division