

65

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Mackinac</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>44N</u> R <u>11W</u>	<u>K4</u>
	T <u>44N</u> R <u>11W</u>	<u>K3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Aug 19 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3										●		
4	7	8	9	10	11	12				●		
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(K4) Quarter corner common to Sections 11-12. Corner reestablished in 1980 by Billy D. Buckler, RLS: "Restored corner midway and on line bet. two Sec. Cors. No evidence of original corner. Placed 1" pipe with 4" aluminum cap. No new witnesses available. Corner lies in an open clear cut area."

(K3) Corner common to Sections 1-2-11-12. Corner reestablished in 1969 by Billy D. Buckler, RLS: "This corner placed in intersection of an old road east and west; an old RR grade north and south. This position is nearly equi-distant between Sec. Cors., one mile to east and to west. Corner monument 1 1/4" x 30" iron pipe, buried in road intersection. 12" Hard Maple(S11 NBT) S44W 22.7', 8" Hard Maple(S12 NBT) S59E 25.7'"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K4) Recovered the 1980 monument as described, a 1" ID iron pipe capped with a 4" dia. cast aluminum MDNR tablet, 0.28' South and 0.52' West of the record position. I accepted the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked four bearing trees as described below. Corner recovered and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

(K3) Recovered the 1969 monument as described, in good condition, and at record bearing and distance from the two 1969 witness trees. Left the monument in place and made two new accessories as described below. Corner recovered and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K4) Found 1" iron pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:

10" Maple S20E 17.1' "1/4S NBT"
8" Maple S80W 30.2' "1/4S NBT"
6" Twin Cherry N43E 16.4' "1/4S NBT"
8" Maple S75E 23.4' "1/4S NBT"

Bearings are magnetic. Placed a 4" squared and scribed cedar post adjacent.

(K3) Found 1 1/4" iron pipe. Blazed, scribed, and set measuring nails in the following:

16" Maple S45W 23.0' "S11" (1969 wit)
12" Maple S53E 26.0' "S12" (1969 wit)
14" Maple N38E 43.4' "S1 NBT"
12" Maple S70E 37.4' "S12 NBT"

Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/18/98

For the Michigan Department of Natural Resources - Forest Management Division