

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Hackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling In Section	S 12 T 44N R 11W	6
	S 12 T 44N R 11W	5
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Aug 14 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(6-Sec. 12) Northeast 1/16 corner, Section 12. Corner not established in the original survey. Found no subsequent record.  
(5-Sec. 12) North 1/16 corner, Section 12. Corner not established in the original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(6-Sec. 12) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners 1315.32' N, 1333.03' E, 1333.03' W, and 1315.35' S. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

(5-Sec. 12) found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1313.88' North and Center of Section 1313.88' South. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(6) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 8" Maple S18E 13.0'      "N1/16 BT" 4" Maple S70E 6.3'      "N1/16 BT" 6" Maple N74W 7.5'      "N1/16 BT" 10" Maple N20W 20.6'    "N1/16 BT" Bearings are magnetic. Placed a 3" squared and scribed cedar post adjacent.	(5) Set 1" ID pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 10" Maple N81E 3.05'      "N1/16 BT" 12" Maple M40E 13.3'      "N1/16 BT" 14" Maple North 18.6'      "N1/16 BT" 14" Maple N78W 10.75'    "N1/16 BT" Placed a 3" squared and scribed cedar post adjacent.
---	--



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 11/18/98

For the Michigan Department of Natural Resources - Forest Management Division