

70

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T 44N R 11W 13

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Sep 29 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3									●				
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(13) Corner common to Sections 2-3-10-11. Corner perpetuated in 1969 by Billy D. Buckler, RLS: "This corner replaced at an old iron pipe. Found this pipe at intersection of old trail roads to south and east. Corner monument 1" pipe with 4" aluminum cap. 16" Hard Maple (S3 N8T) N19W."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(13) Recovered the 1969 monument as described, a 1" ID iron pipe capped with a 4" dia. MDNR tablet, in good condition, and at record bearing from the single witness tree (note no distance on the record). Measured to adjacent section corners as follows: 78.0396 ch. north (78.44 GLO), 80.4213 ch. east (80 GLO), and 79.8748 ch south (80 GLO). Billy D. Buckler noted in 1972 that "Partial retracement of this township discloses considerable excess in the East-West lines...I believe this condition may be found throughout T44N R11W, as well as the adjacent township to the West." I accepted the monument as a careful and faithful reestablishment of the position of the original corner. Left the monument in place and marked new witnesses as described below. Corner recovered and re-witnessed by T. Stark and M. Feldpausch, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(13) found 1" pipe with 4" MDNR cap.
Blazed, scribed, and set measuring nails
in the following:
20" Maple N18W 75.2' "S3 N8T" ('69 wit)
12" Twin cherry S67W 76.8' "S11 N8T"
24" W. Pine N76W 63.2' "S3 N8T"
8" Cherry N04E 56.2' "S2 N8T"
Corner lies in a new fence line.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/10/98

For the Michigan Department of Natural Resources - Forest Management Division