

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T44N R 11W LI _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Oct 12 1998

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(L1) Quarter corner common to Section 1 T44N-R11W and Section 36 T45N-R11W. Corner established in 1841 by John Burt: "West on south side of section 36 (T45N R11W)...40.00 set qr. section post. Sugar 16 N55E 28, Birch 16 N26W 15...80.00 set post corner of sections 35 & 36". This corner was reestablished in 1979 by Billy D. Buckler, ALS, by the method of single proportionate measurement, but the position was not monumented. Buckler measured 5326.4' between K1 and M1. He used the SPM position to control his 1979 subdivision of Section 1.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L1) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record - midway and on a line of mean true bearing between reestablished section corners 2661.66' east and west. The observed mean true bearing of this line was S89 deg. 48' 55"E. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L1) Set 1" pipe with 4" MDNR cap.
 Blazed, scribed, and set measuring nails
 in the following:
 14" Ironwood N60E 12.4' *1/4S NBT*
 20" Maple N22E 18.2' *1/4S NBT*
 10" Maple N77W 26.3' *1/4S NBT*
 8" Maple S48W 18.4' *1/4S NBT*
 Placed a squared cedar post adjacent.
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/18/98

For the Michigan Department of Natural Resources - Forest Management Division