

JAN 21 1999

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Mackinac County Remonumentation Corner

For corners in

- |                                    |   |                        |
|------------------------------------|---|------------------------|
| Mackinac County                    | Located in:                                 | Corner Code #          |
| 1. Public Land Survey              | T44N R11W<br>T45N R11W<br>T R<br>T R<br>T R | G-1<br>G-13 (Luce Co.) |
| 2. Property Controlling in Section | S T R                                       |                        |
| 3. Miscellaneous Property in Sec.  | S T R                                       |                        |
| 4. Lot No. , Recorded Plat         | S T R                                       |                        |
| 5. Private Claims                  | S T R                                       |                        |

RECEIVED & FILED  
DIANE FRANKOVICH  
MACKINAC COUNTY REGISTER OF DEEDS

DEC 31 1998

AM PM  
7|8|9|10|11|12|1|2|3|4|5|6

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 11-20-98 NEM

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11				12
5													
6	18		17		16		15		14				13
7													
8	19		20		21		22		23				24
9													
10	30		29		28		27		26				25
11													
12	31		32		33		34		35				36
13													

*T44N R11W*

I, William L. Karr, in a field survey on December 2, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G-1) Section Corner Common to Sections 33 & 34, T. 45 N., R. 11 W. and Sections 3 & 4, T. 44 N., R. 11 W.

1841 John Burt set a post for the corner in the original survey.

Witnesses: 7" Tamarack N 34° E 14 lks  
8" Tamarack N 44° W 32 lks

Could find no subsequent history on this corner in the available public records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G-1) Section Corner Common to Sections 33 & 34, T. 45 N., R. 11 W. and Sections 3 & 4, T. 44 N., R. 11 W.  
This corner is being perpetuated as part of the Luce County Remonumentation Program.

Found probable evidence of the original 8" Tamarack B.T. Found a hollow tamarack stump with evidence of a base blaze at the proper location. Could find no evidence of the tamarack to the Northeast or of the original post. The position for the corner works well with other recovered evidence along the township line. Re-established the corner position at the record bearing and distance from the B.T. stump.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G-1) Section Corner Common to Sections 33 & 34, T. 45 N., R. 11 W. and Sections 3 & 4, T. 44 N., R. 11 W.

Corner is a 1/2" x 48" re-bar with a stamped Luce County Remonumentation cap. The corner falls in a very wet, partially flooded area.

Witnesses: Cedar Post North 1.0'  
Cedar 8" N 78° E 12.32'  
Tamarack 8" S 57° E 22.80'  
Cedar 7" N 89° W 10.04'  
Cedar 8" N 16° W 18.11'  
Charred remains of rubber boots West 30' +/-

Bearings are compass bearings, corrected for declination, all distances are to a nail and tag in the side of the witness object, unless otherwise noted.



Signed by William L. Karr

Date 12/22/98

Surveyor's Michigan License No. 27450