

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 44N N.R. 12W


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 28-29

CORNER MONUMENT 1" pipe with 4" brass cap.

DATE MONUMENT PLACED AND WITNESSED 8-15-62

WITNESSES TO CORNER..... 14" Y. Birch (1/4 S NBT) N75°W, 17 1/2 links



7" Hard Maple (1/4 S NBT) S 50°W, 26 1/2 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner replaced at old cedar stake in N-S fenceline. Found a down Beech with an old face and numerous blazes bearing N73°E, 48 links. Record notes indicate a beech at N73°W, 48 links. Distance south to swamp checks.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 7, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler