

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ~~44~~ NR. 12 - W.

----- Mackinaw ----- COUNTY

DESCRIPTION OF CORNER ~~Section Corner common to Sections 27, 28, 33, 34~~ -----

DESCRIPTION OF CORNER MONUMENT ~~1" Pipe with 4" Brass cap~~ -----

WITNESSES TO CORNER ~~10" Cedar - North - 30 Links~~ -----

~~14" Cedar - S. 28 W. - 57 Links~~ -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this Township. One probable original B.T. still in place, in poor condition.

Corner was placed and witnessed April 17, 1952.

SURVEYORS SEAL

SIGNED *Alan C. DeLoe* DATE 11/10/52
REGISTERED LAND SURVEYOR