

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 44 NR. 12 W.

MacKinnon COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 22 & 27

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap

WITNESSES TO CORNER 14" S. Maple - 8.6 W - 5 Links

8" Elm - N 7 W - 33 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew, while making a partial resurvey of this area. One original B.T. in place. The face from the bearing tree has been chopped out by a souvenir hunter, but corner was proven from Meander corner 2 chains East, which has a good original B.T. in evidence.

Corner was placed and witnessed January 10, 1952.

SURVEYORS SEAL

SIGNED Sean C. Seaman DATE 1/16/52  
REGISTERED LAND SURVEYOR