

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>44</u> N. R. <u>12</u> W.	<u>H-11, H-10, G-10</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-3, 1988, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- H-11 South 1/4 Corner of Section 27. Corner placed by D. C. DeLaMater R.L.S. 4-18-52 Witness Trees: 12" H. Maple, East 41.58' & 10" Beech, N35°W, 36.3'.
- H-10 Center of Section 27. Not previously set.
- G-10 West 1/4 Corner of Section 27. OBT'S: Cedar 8, S35°W, 8 lks. & Cedar 12, S39°E 5 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-11 Re-witness corner as set by D. DeLaMater in 1952.
- H-10 Corner set at intersection of N-S 1/4 line and E-W 1/4 line of Section 27.
- G-10 West 1/4 Corner of Section 27 set midpoint on line between N.W. Corner and S.W. Corner of Section 27.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
DNR MONUMENTS AT ALL THREE CORNERS.

- | | | |
|-------------------------------------------|-------------------------------|-----------------------------|
| H-11 10" Maple, N56°E, 19.7' | H-10 8" Tamarack, S3°W, 20.9' | G-10 4" Cedar, S40°E, 4.25' |
| 8" Maple, S78°E, 24.8' | 6" B. Ash, N12°W, 28.4' | 5" Cedar, S56°W, 8.4' |
| DeLaMater's Witnesses are still in place. | 10" Cedar, N57°W, 40.7' | 6" Cedar, N23°W, 19.9' |
| | 8" Cedar, N85°W, 96.6' | 6" Cedar, East, 9.6' |

SIGNED BY Gerald L. Wiggins DATE 12-5-88


SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____



(SEAL)