

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MACKINAC CO.

3 CORNERS

| FOR CORNERS OF—:                           | LOCATED IN—:                    | CORNER CODE NUMBER |
|--|---------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY _____                | T. <u>44</u> N. R. <u>12</u> W. | A-2, B-3, C-10     |
| 2. PROPERTY CONTROLLING IN SECTION _____   | T. _____ N. S. R. _____ E. W.   |                    |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S. R. _____ E. W.   |                    |
| 4. LOT NO. _____, RECORDED PLAT _____      |                                 |                    |
| 5. PRIVATE CLAIMS _____                    |                                 |                    |

*Filed 6-10-89*

REGISTER OF DEEDS STAMP AND FILING NUMBER \_\_\_\_\_

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3-23, 5-24, 5-25, 1989, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- A-2 West 1/4 Corner of Section 6. OBT'S: Cedar 20", S85°E, 22 lks. & Cedar 24", N59°W, 20 lks.
- B-3 South 1/4 Corner of Section 6. OBT'S: Sugar 14", S69°E, 37 lks. & Sugar 12", S12°W, 39 lks.
- C-10 West 1/4 Corner of Section 29. OBT'S: Cedar 12", S62°E, 17 lks. & Fir 6", N31°W, 18 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-2 Corner set by single proportionate measure between the N.W. Corner and the S.W. Corner of Section 6. Swamp edge and creek to South fit original measure.
- B-3 Corner set on line between S.W. Corner and S.E. Corner of Section 6 and in line with old fence to North and South.
- C-10 Corner set midpoint on line between M.W. Corner and S.W. Corner of Section 29.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                         |                           |                         |
|-------------------------|---------------------------|-------------------------|
| A-2 DNR Monument        | B-3 1" Pipe w/plastic cap | C-10 DNR Monument       |
| 6" Balsam, N32°W, 18.9' | 10" Maple, N66°W, 54.5'   | 6" Cedar, N55°E, 33.3'  |
| 6" Balsam, N41°E, 27.2' | 6" Maple, S44°W, 47.8'    | 6" Cedar, N15°W, 31.2'  |
| 7" Spruce, N63°E, 23.0' | 4" Maple, S21°W, 30.9'    | 10" Cedar, S60°E, 33.5' |
| 5" Balsam, S35°E, 22.0' | 36" Maple, S35°E, 49.0'   | 5" Cedar, South, 34.9'  |

SIGNED BY Gerald L. Wiggins DATE 6-14-89

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET