

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MACKINAC CO.

2 CORNERS

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N., R. <u>12</u> W.	<u>E-9, E-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S., R. _____ E.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S., R. _____ E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 2-6 & 2-27, 1989, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

E-9 N.W. Section Corner of Section 28 and Meander Corner. OBT'S: Maple 12", S13°W, 77 lks. & Black Ash 10", S1°E, 105 lks.

E-11 S.W. Section Corner of Section 28. Corner set by G. Wilcox's on 7-10-73. Witness: 5" Pine, N80°W, 5.6' & 7" Pine, S80°E, 7.33' & 6" Pine, N35°E, 26.82'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-9 Corner set by proportionate measure from original meander corner to East, by doubling the distance of the South 1/2 mile between sections 28 and 29. By record distance West to edge of Lake. Distance South to swamp edge and edge of lake fit record distance. Distance North to center line of east-west road compares with 1/2 mile South.

E-11 Corner set from 3 witness trees marked by G. Wilcox on 7-10-73. His monument had been pulled out. Replaced his re-rod, and also placed DNR Monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9 DNR Monument

E-11 DNR Monument

Sq. Post, South, 0.3'  
14" Maple, N26°W, 34.1'  
14" Maple, S85°W, 28.0'  
6" B. Ash, S51°W, 54.8'

10" Cedar, S34°E, 21.2'  
6" Cedar, N21°E, 46.6'  
Wilcox's 3 witness trees are still green.

SIGNED BY \_\_\_\_\_

Gerald L. Wiggins  
Gerald L. Wiggins

DATE 6-14-89

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_

CHIEF OF SURVEY PARTY

DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

DATE \_\_\_\_\_

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET

