

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

MACKINAC CO.

3 CORNERS.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>44</u> N., R. <u>12</u> W.	<u>E-8</u>
2. PROPERTY CONTROLLING IN SECTION <u>20</u>	T. <u>44</u> N., R. <u>12</u> W.	<u>11, 14</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N., R. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

8-10-89
GW

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-25, 1989, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-8 East 1/4 Corner of Section 20. OBT'S: Beech 16", N52°W, 14 lks. & Sugar 20", N53°E, 25 lks.
- 11 S.W. 1/16 Corner of Section 20. Not previously set.
- 14 South 1/16 Corner on east side of Section 20. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-8 Set in center line of east-west road and in line with road to south and in line with fence to north.
- 11 Corner set at center of S.W. 1/4 of Section 20.
- 14 Corner set midpoint on line between East 1/4 corner and S.E. Section Corner of Section 20.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|----------------------------|-------------------------|-------------------------|
| E-8 1" Pipe w/plastic Cap. | 11 DNR Monument | 14 DNR Monument |
| P. Pole, N78°E, 95.6' | 6" Maple, S4°E, 46.8' | 10" Cedar, S55°W, 36.2' |
| Stop Sign, S18°E, 44.9' | 5" Beech, S70°W, 16.1' | 8" Cedar, N70°W, 34.5' |
| 10" Spruce, N60°W, 83.9' | 8" Maple, N84°W, 28.7' | 5" Cedar, N25°E, 4.5' |
| 24" Maple, N2°E, 48.7' | 10" Maple, N45°E, 15.3' | 8" Cedar, S65°E, 5.0' |

SIGNED BY Gerald L. Wiggins DATE 6-14-89

Gerald L. Wiggins

SURVEYOR'S MICHIGAN REGISTRATION NO. 23521


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET