

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

23

For corners in

Mackinac Located in: Corner Code #
(County)

1. Public Land Survey T R
T R
T R
T R

2. Property Controlling S 6 T 11 R 12
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

May 13 1998
I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
(9-Sec. 6) East 1/16 corner of Section 6. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(9-Sec. 6) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Quarter corner 1281.34' East and Center of Section 1281.34' West. At the position for the corner, which is located on top of the cut stump of a 12" cedar, I placed an 8" long iron spike driven through a yellow plastic cap stamped "MICH DNR PS 33986". I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped, adjacent to the stump. The pipe is bent over so that the tablet is above the spike. Corner placed and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(9) Set 8" iron spike with yellow plastic cap in 12" cedar stump. Blazed, scribed, and set measuring nails in the following:
6" Cedar N40E 18.2' "E1/16 BT"
10" Cedar S38E 16.0' "E1/16 BT"
12" Cedar N05E 7.65' "E1/16 BT"
5" Cedar S60W 9.05' "E1/16 BT"
Placed a 4" squared and scribed cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 8/18/98

For the Michigan Department of Natural Resources - Forest Management Division