

24

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Mackinac	Located in:	Corner Code #
(County)		
1. Public Land Survey	T <u>44R</u> <u>12N</u>	<u>C2</u>
	T <u>   </u> <u>   </u>	<u>   </u>
	T <u>   </u> <u>   </u>	<u>   </u>
	T <u>   </u> <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

May 13 1998

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(C2) Quarter corner common to Sections 5-6. Corner established in 1849 by Guy M. Carleton: "40.00 Set post for quarter section corner. Cedar 12 S4W 29 links, Cedar 12 N28E 33 links". Corner shown on Survey Report by Thomas P. O'Brien, PS 21274, dated Feb. 28, 1978. No monumentation specified. The corner is shown North, 2640' from the SE corner of Section 6. Corner shown on sketch made by William F. Bowman, dated 8/8/88 as 2640.0' northerly (no bearing shown) of Westerly of two monuments at the SE corner of Sec. 6, and monumented with "Set 18 and cap". Wood post recovered in 1989 by G.L. Wiggins PS 23521. Wiggins accepted the post as marking the corner and subdivided section 6.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(C2) Original post and accessories not recovered. I found a wood post N 00deg. 04' 20"E (true brg) 2639.64' from the westerly of two monuments recovered (those as previously recorded by Feindt in 1974) at the location of the SE corner of Section 6. I retraced the O'Brien survey and the Wiggins survey and conclude that the post represents the location of the Quarter corner as described by them. I did not find the 18 with cap noted by Bowman. I accept the post as a careful and faithful reestablishment of the position of the original corner and, in it's place, set a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. Corner placed and witnessed by T.Stark and M.Feldpausch, Newberry District Office.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(C2) 1" pipe with 4" MDNR cap.  
 Blazed, scribed, and set measuring nails  
 in the following:  
 4" Cedar N45E 6.6'      "1/4S NBT"  
 8" Cedar S50E 18.15'    "1/4S NBT"  
 10" Cedar S24E 15.4'    "1/4S NBT"  
 3" Cedar S33W 5.9'      "1/4S NBT"  
 Placed a 3" squared and scribed cedar  
 post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 8/18/98  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division