

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac
 (County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-------------------------|------------|
| 1. Public Land Survey | T | <u>44N</u> | R | <u>12W</u> | <u>H11</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | <u>27</u> | T | <u>44N</u> R <u>12W</u> | <u>15</u> |
| | S | _____ | T | _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ R _____ | _____ |
| | S | _____ | T | _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

Nov 05 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11				●								
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H11) Quarter corner common to Sections 27-34. Corner recorded in 1988 by Gerald L. Wiggins, RLS: Re-witness corner as set by D.DeLaMater in 1952. DNR monument at corner. 10" Maple N56E 19.7', 8" Maple S78E 24.8'. DeLaMater's 1952 witness trees are: 12" H.Maple East 63 links, 10" Beech N35W 55 links.
 (15-Sec. 27) West 1/16 corner between Sections 27-34. Corner established in 1958 and recorded in 1960 by Billy D. Buckler, RLS. 2"x36" iron pipe. 10" Y. Birch S53E 3 links, 10" Hard Maple N05W 70 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H11) Recovered the 1952 monument, a 1" ID iron pipe capped with a 4" dia. brass State of Michigan tablet, in good condition, and at record bearing and distance from the remaining NBT's: The 1988 10" Maple is now a stump with blaze visible, the 8" is in good condition. The 1952 Maple is in good condition with blazes overgrown. The 1952 beech was not recovered. Left the monument in place, made new BH markings on the 1952 NBT, and made two new witnesses as described below.
 (15-Sec. 27) Recovered the 1958 monument as described, in good condition, and at record bearing and distance from the record accessories. The Y.Birch is now a stump with no markings visible. The Hard Maple is in good condition with overgrown blaze. Left the monument in place, made new BH blaze on the 1958 Maple, and made three new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H11) Found 1" pipe with 4" brass cap. Blazed, scribed, and set measuring nails in the following: 9" Maple S78E 25.3' "1/4S NBT" 16" Maple S87E 41.8' do 10" Beech N40W 36.75' do A Power pole D-58 6-5, bears N05E, 37.0' distant. Bearings are magnetic. Distances to nail w/tag. Monument is set flush with ground.	(15) Found 2" iron pipe. Blazed, scribed, and set measuring nails in the following: 14" Maple N02W 45.95' "W1/16 BT" 6" Maple N39W 49.35' do 10" Maple N82E 10.8' do 12" Maple N35E 62.6' do Bearings are magnetic. Distances are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski Date 4/18/00
 Surveyor's Michigan License No. 33486