

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

 (County)

Located In: _____ Corner Code #/## _____

- | | | | | | |
|------------------------------------|---|------------|---|------------|------------|
| 1. Public Land Survey | T | <u>44N</u> | R | <u>12W</u> | <u>G11</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Nov 05 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


(G11) Corner common to Sections 27-28-33-34. Reestablished in 1952 by Dean C. DeLaMater, RLS. 1" pipe with 4" brass cap. 10" Cedar North 30 links, 14" Cedar S28W 57 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G11) Recovered the 1952 monument as described, a 1" ID iron pipe capped with a 4" dia. brass State of Michigan tablet, appropriately stamped, in good condition, and at record bearing and distance from the 1952 cedar NBT's, both recovered in good condition with blazes overgrown. Left the monument in place, marked new BH blazes on the 1952 witnesses, and marked two new trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G11) Found 1" pipe with 4" brass cap. Blazed, scribed, and set measuring nails in the following:
 16" Cedar N04W 20.3' "S28"
 20" Cedar S36W 37.9' "S33"
 14" Cedar N36W 6.3' "S28 NBT"
 10" Cedar S88E 31.7' "S34 NBT"
 Corner lies on N side of an old E-W trail. Bearings are magnetic. Distances are to nail w/tag.



Signed by Stephan J. Szyszkoski Date 4/18/00
 Surveyor's Michigan License No. 33986