

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>MACOMB</u> (County)	Located In: <u>WARREN</u>	Corner Code # <u>        </u>
1. Public Land Survey	<u>T 1N. R 12E.</u>	<u>A-4</u>
	<u>T     R     </u>	<u>        </u>
2. Property Controlling in Section	<u>S     T     R     </u>	<u>        </u>
	<u>S     T     R     </u>	<u>        </u>
3. Miscellaneous Property in Sec.	<u>S     T     R     </u>	<u>        </u>
	<u>S     T     R     </u>	<u>        </u>
4. Lot No. <u>        </u> , Recorded Plat <u>        </u>		
5. Private Claims <u>        </u>		

SUBJECT &  
REMONUMENTATION

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

I, **STEVEN E. DUNN**, in a field survey on **JUNE 6, 1998**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NO GLO POST

PLATS	L.23, P.39	SUPERVISOR'S PLAT OF EYESTER-CROMIE DEQUINDRE FARMS	AUG. 23, 1946
	L.74, P.34 & 35 (OCR)	SHIRLEY JEAN SPOON SUBDIVISION	SEP. 22, 1954
	L.87, P.6 & 7 (OCR)	MOULIN ROUGE SUBDIVISION NO. 2	AUG. 15, 1956
	L.91, P.14 (OCR)	MADISON MANOR SUBDIVISION	JUN. 3, 1957
	L.50, P.1	BARBARY SUB.	FEB. 5, 1962
	L.51, P.1	BARBARY SUB. NO. 2	SEP. 24, 1962
	L.126, P.24-26 (OCR)	EASTWOOD MANOR SUB.	MAY 19, 1969
	L.132, P.30-32 (OCR)	NORTHWOOD MANOR SUB.	OCT. 13, 1971
	L.252, P.20-22 (OCR)	SOUTHWOOD MANOR SUB.	MAR. 4, 1997

L.C.R.C.: L.17530, P.360 (OCR) HUSTON K. KENNEDY #17623 M-4, T.1N., R.11E. AUG. 28, 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
A-4 1/4 SECTION CORNER.

FOUND 1/2" IRON ROD IN A MONUMENT BOX IN CONCRETE PAVEMENT IN THE CENTERLINE OF DEQUINDRE.

I VERIFIED THE LOCATION BY COMPARING MEASURED DISTANCES AND ANGLES TO RECORDED DISTANCES AND ANGLES OF ITEMS LISTED ABOVE.

FIELD MEASUREMENTS AND RECORD MEASUREMENTS:

A-4 TO A-5 2699.49' FIELD      A-4 TO A-3 2707.92' FIELD      A-4 TO M-4, T.1N., R.11E. 49.32' LCRC L. 17530, P.360 (OCR) 49.30' FIELD

A-4 TO M-3, T.1N., R.11E. 2651.62' SOUTH MANOR 2650.19' FIELD

ACCEPTED BY THE MACOMB COUNTY SURVEY PEEF GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9/29/98

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
A-4 1/4 SECTION CORNER

William E. Soderberg  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

I REPLACED THE FOUND 1/2" IRON ROD WITH A 3/4" BY 24" IRON ROD WITH ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN EXISTING MONUMENT BOX.

WITNESSES:

- S.48°W. 34.82' NE CORNER OF CATCH BASIN CASTING.
- S.48°W. 77.81' STEEL FENCE POST.
- S.52°E. 34.95' NW CORNER OF CATCH BASIN CASTING.
- N.89°E. 45.34' SET MAG NAIL W/MACOMB COUNTY REMONUMENTATION WITNESS TAG IN SOUTH FACE OF UTILITY POLE.
- N.19°E. 117.70' CENTER TOP NUT OF FIRE HYDRANT.
- SOUTH 49.30' FOUND BRASS CAP STAMPED "OAKLAND COUNTY REMONUMENTATION CORNER #17623" IN A MONUMENT BOX IN ASPHALT CAPPED CONCRETE PAVEMENT AT THE CENTERLINE DEQUINDRE. CORNER IS M-4, T.1N., R.11E., OAKLAND COUNTY.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn Date Sept. 29, 1998

Surveyor's Michigan License No. 28408 868

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983