

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

OAKLAND COUNTY  
 REGISTER OF DEEDS

For corners in

<u>MACOMB</u> (County)	Located In: <u>WARREN</u>	Corner Code # <u>A-6</u>
1. Public Land Survey	<u>T 1N. R 12E.</u> T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on JUNE 6, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH FLETCHER-1816
- |                        |  |               |
|------------------------|--|---------------|
| PLATS                  | URBANREST SUBDIVISION                                  | NOV. 8, 1921  |
| L.5, P.4               | PHILLIPS MANOR SUBDIVISION                             | AUG. 19, 1925 |
| L.39, P.13 (O.C.R.)    | BEAUTY BUILT MANOR SUB.                                | MAY 24, 1957  |
| L.91, P.7 (O.C.R.)     | MADISON OAKS SUB.                                      | MAR. 31, 1958 |
| L.94, P.31 (O.C.R.)    | STEVEN HEIGHTS SUB.                                    | APR. 3, 1958  |
| L.94, P.34 (O.C.R.)    | GREENBRIAR ESTATES SUB.                                | MAY 4, 1962   |
| L.50, P.12             | ST. LOUISE SUB.  | AUG. 13, 1996 |
| L.80, P.45 & 46        |  |               |
| L.C.R.C.:              | EDWARD PATRICK O'ROURKE FOUND MON. BOX W/5/8" IRON BAR | DEC. 26, 1972 |
| L.2355, P.456          | TERENCE B. CANTRELL FOUND 1/2" IRON ROD IN HANDHOLE    | AUG. 30, 1974 |
| L.6358, P.659 (O.C.R.) | GEORGE M. PLATZ FOUND 1/2" IRON ROD IN MONUMENT BOX    | JUN. 1, 1993  |
| L.5878, P.424          | JOSEPH C. KAPELCZAK #24598                             | JAN. 2, 1998  |
| L.17933, P.110(O.C.R.) | SET OAKLAND COUNTY REMONUMENTATION BRASS CAP           |               |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 A-6 1/4 SECTION CORNER. CORNER IS COMMON WITH M-6, TOWN 1 NORTH, RANGE 11 EAST, OAKLAND COUNTY.  
 FOUND BRASS CAP STAMPED "OAKLAND COUNTY REMONUMENTATION CORNER #24598" IN A MONUMENT BOX IN ASPHALT CAPPED CONCRETE PAVEMENT AT THE CENTERLINE OF DEQUINDRE.  
 I VERIFIED THE LOCATION BY COMPARING MEASURED DISTANCES AND ANGLES TO RECORDED DISTANCES AND ANGLES OF ITEMS LISTED ABOVE. CORNER ALSO MATCH THE WITNESS TIES OF ABOVE L.C.R.C.'s.

- FIELD MEASUREMENTS AND RECORD MEASUREMENTS:
- |                          |  |
|--------------------------|--|
| A-6 TO A-5               | A-6 TO A-7   |
| 2640.00' (GLO 40 CHAINS) | 2640.00' (GLO 40 CHAINS)   |
| 2630.56' FIELD           | 2639.23' FIELD   |
| L.C.R.C. L.2355, P.456   | PK NAIL IN SOUTH FACE OF UTILITY POLE.                                       |
| N.56°W. 59.12'           | PK NAIL IN NORTH FACE OF UTILITY POLE.                                       |
| N.90°E. 51.81            |  |
| L.C.R.C. L. 5878, P.424  | SET PK NAIL W/SDA TAG IN SE FACE UTILITY POLE.                               |
| AZ. 203° 116.39'         | FOUND PK NAIL W/TAG IN SOUTH FACE UTILITY POLE.                              |
| AZ. 298° 59.10'          |  |
| L.C.R.C. L.17933, P. 110 | SET NAIL WITH REMONUMENTATION TAG IN NORTH SIDE POWER POLE.                  |
| EAST 51.90'              | PK NAIL WITH REMONUTATION TAG SE SIDE STREET LIGHT POLE WITH CROSSWALK SIGN. |
| S.23°W. 116.59'          | PK NAIL WITH REMONUTATION TAG SOUTH SIDE POWER POLE.                         |
| N.62°W. 59.24'           |  |



I ACCEPTED THE LOCATION OF THE FOUND OAKLAND COUNTY REMONUMENTATION BRASS DISK AS THE CORNER.  
 C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 A-6 1/4 SECTION CORNER  
 BRASS CAP ON 3/4" IRON ROD STAMPED "OAKLAND COUNTY REMONUMENTATION #24508" IN A MONUMENT BOX.

- WITNESSES:
- |                 |   |
|-----------------|---|
| S.21°W. 116.48' | FOUND PK AND OCR TAG IN SE FACE UTILITY POLE. |
| S.21°W. 116.39' | FOUND PK W/SDA TAG IN SE FACE UTILITY POLE.   |
| N.64°W. 59.14'  | FOUND PK AND OCR TAG IN SW FACE UTILITY POLE. |
| N.64°W. 59.09'  | FOUND PK W/TAG IN SW FACE UTILITY POLE.       |
| N.87°E. 51.84'  | FOUND PK NAIL IN NORTH FACE UTILITY POLE.     |
| S.57°W. 52.22'  |   |

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.  
 Signed by Steven E. Dunn Date SEP 29, 1998  
 Surveyor's Michigan License No. 28408

ACCEPTED BY THE MACOMB COUNTY SURVEY PEEB  
 OFFICE AS THE OFFICIAL CORNER UNDER MICHIGAN  
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD  
 ON 9/29/98  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN