

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

OAKLAND COUNTY  
 REMONUMENTATION

For corners in

|  |                              |                                  |
|--|------------------------------|----------------------------------|
| <u>MACOMB</u><br>(County)                                  | Located In:<br><u>WARREN</u> | Corner Code #<br><u>        </u> |
| 1. Public Land Survey                                      | <u>T 1N R 12E</u>            | <u>A-13</u>                      |
|  | <u>T    R   </u>             | <u>        </u>                  |
|  | <u>T    R   </u>             | <u>        </u>                  |
|  | <u>T    R   </u>             | <u>        </u>                  |
| 2. Property Controlling in Section                         | <u>S    T    R   </u>        | <u>        </u>                  |
|  | <u>S    T    R   </u>        | <u>        </u>                  |
| 3. Miscellaneous Property in Sec.                          | <u>S    T    R   </u>        | <u>        </u>                  |
|  | <u>S    T    R   </u>        | <u>        </u>                  |
| 4. Lot No. <u>        </u> , Recorded Plat <u>        </u> |                              |                                  |
| 5. Private Claims <u>        </u>                          |                              |                                  |

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on JUNE 6, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH FLETCHER-1816

PLATS:

|                       |  |               |
|-----------------------|--|---------------|
| L. 16, P. 27 (O.C.R.) | OAKWAY SUBDIVISION                           | DEC. 16, 1916 |
| L. 18, P. 5 (O.C.R.)  | FORD-OAK SUBDIVISION                         | MAY 10, 1917  |
| L. 7, P. 27           | JOHN B. SOSNOSKI EIGHT MILE ROAD SUBDIVISION | DEC. 22, 1923 |
| L. 34, P. 54 (O.C.R.) | SUPERVISOR'S PLAT NO. 2                      | JULY 24, 1936 |

L.C.R.C.:

|                         |   |              |
|-------------------------|---|--------------|
| L. 1793, P.118 (O.C.R.) | JOSEPH C. KAPELCZAK #24508 SET OAKLAND COUNTY REMON. BRASS CAP. | JAN. 2, 1998 |
| L.29356, P.107 (W.C.R.) | MARTIN C. DUNN #30081 SET WAYNE COUNTY REMON. CORNER            | DEC. 6, 1996 |

MDOT RIGHT-OF-WAY MAP: SHEET 1

REV. 9-1981

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 SECTION CORNER. CORNER IS A COMMON CORNER COMMON TO M-13, T. 1 N., R. 10 E., OAKLAND COUNTY. M-1, T.1S., R.11E., WAYNE COUNTY, AND A-1, T.1S., R.12E., WAYNE COUNTY

FOUND BRASS CAP STAMPED "OAKLAND COUNTY REMONUMENTATION CORNER #24598" IN A MONUMENT BOX IN ASPHALT CAPPED CONCRETE PAVEMENT.

I VERIFIED THE LOCATION BY COMPARING MEASURED DISTANCES AND ANGLES TO RECORDED DISTANCES AND ANGLES OF ITEMS LISTED ABOVE. CORNER ALSO MATCHED THE 4 WITNESS TIES OF ABOVE L.C.R.C.'S

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

|                |                             |                 |
|----------------|-----------------------------|-----------------|
| A-13 TO B-13   | A-13 TO A-12                | ANGLE           |
| 2647.18' FIELD | 2640.00' (GLO 40 CHAINS)    | A-12/A-13/B-13  |
| 2648.00' PLAT  | 2635.26' FIELD              | 90°19'45" FIELD |
|                | 2635.77' S. P. # 2 (O.C.R.) | 90°18'30" MDOT  |
|                |                             | 90°21'45" PLAT  |

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD 7/28/98  
William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

L.C.R.C.'S

|                         |                |  |
|-------------------------|----------------|--|
| L.1793, P. 118 (O.C.R.) | N.57°E. 61.28' | FOUND PK NAIL WITH OAKLAND COUNTY WITNESS TAG IN NW SIDE OF STRAIN POLE        |
|                         | S.49°E. 91.81' | FOUND PK NAIL WITH OAKLAND COUNTY WITNESS TAG SW SIDE OF STRAIN POLE.          |
|                         | S.54°W. 93.97' | FOUND PK NAIL WITH OAKLAND COUNTY WITNESS TAG NE SIDE OF STRAIN POLE.          |
|                         | N.77°W. 88.14' | FOUND PK NAIL WITH OAKLAND COUNTY WITNESS TAG NE SIDE OF LIGHT POLE.           |
| L.29356, P.107 (W.C.R.) | N.65°E. 61.31' | FOUND PK NAIL WITH WAYNE COUNTY WITNESS TAG NW SIDE OF UTILITY POLE.           |
|                         | S.36°E. 91.74' | FOUND PK NAIL WITH WAYNE COUNTY WITNESS TAG SW SIDE OF UTILITY POLE IN MEDIAN. |
|                         | S.62°W. 94.03' | FOUND FORM NAIL WITH M.S.H.D. TAG  |
|                         | N.79°W. 88.19' | FOUND PK NAIL WITH WAYNE COUNTY WITNESS TAG NE SIDE OF UTILITY POLE.           |

I ACCEPTED THE LOCATION OF THE FOUND OAKLAND COUNTY REMONUMENTATION BRASS CAP AS THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 SOUTHWEST CORNER, T.1N., R.12E., MACOMB COUNTY  
 BRASS CAP ON 3/4" IRON ROD STAMPED "OAKLAND COUNTY REMONUMENTATION #24508" IN A MONUMENT BOX.

WITNESSES

|                |   |
|----------------|---|
| N.57°E. 61.28' | FOUND PK NAIL WITH OAKLAND COUNTY WITNESS TAG IN NW SIDE OF STRAIN POLE |
| S.49°E. 91.81' | FOUND PK NAIL WITH OAKLAND COUNTY WITNESS TAG SW SIDE OF STRAIN POLE.   |
| S.54°W. 93.97' | FOUND PK NAIL WITH OAKLAND COUNTY WITNESS TAG NE SIDE OF STRAIN POLE.   |
| N.77°W. 88.14' | FOUND PK NAIL WITH OAKLAND COUNTY WITNESS TAG NE SIDE OF LIGHT POLE.    |

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.



C0865240 LIBER:08571 PAGE:791 09:29A 01/21/1999  
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

Signed by Steven E. Dunn Date Aug. 10, 1998

Surveyor's Michigan License No. 28408

877