

SURVEY & REMONUMENTATION

APR 29 1996

C0247597 LIBER:06753 PAGE:292 01:11P 09/07/1995
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MACOMB</u> <small>(County)</small>	Located In: WARREN	Corner Code #	
1. Public Land Survey	T <u>1N</u> R <u>12E</u>	<u>E-1</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEVEN E. DUNN, in a field survey on MARCH 3, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY JOSEPH WAMPLER 1817

PLATS

L. 4, P. 58-62	ASSESSORS ADDITION TO VILLAGE OF WARREN
L. 7, P. B1	PECK AND SMITZ'S NORTH BROAD ST. SUBDIVISION
M.C.R.C.	MOUND ROAD CONSTRUCTION PLANS

MAY 10, 1920
JUNE 17, 1924
AUG. 1927

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-25-95
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 SECTION CORNER COMMONLY BEING USED AS A COMMON CORNER COMMON TO E-13, T.2N., R. 12 E.

FOUND 1/2" IRON IN MONUMENT BOX IN CONCRETE PAVEMENT.

VERIFIED LOCATION BY COMPARING DISTANCES FROM E-1 TO D-1, E-1 TO F-1, ANGLE D-1/E-1/F-1 TO PLATS AND TAX DESCRIPTIONS AS LISTED BELOW.

FIELD MEASUREMENTS AND RECORDED DISTANCES

E-1 TO D-1	2809.35' M. 2809.00' (ASSESSORS ADDITION TO VILLAGE OF WARREN)
	2809.43' (RECENT PLATS AND TAX DESCRIPTIONS)
E-1 TO F-1	2501.03' M. 2500.70' (PLAT) 2501.73' (TAX DESCRIPTIONS)
E-1 TO E-13	WEST 42 LK. (GLO) 27.72'
ANGLE D-1/E-1/F-1	180°29'56" M. 180°28'30" (PLAT)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 T.1N., R.12E. I REPLACED 1/2" IRON PIPE WITH A 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN AN EXISTING MONUMENT BOX.

WITNESSES

S.46°E.	67.23'	SET PK NAIL WITH M.C.R. WITNESS TAG IN SW FACE UTILITY POLE
N.29°E.	67.63'	SET PK NAIL WITH M.C.R. WITNESS TAG IN SW FACE UTILITY POLE
S.49°W.	80.55'	SET PK NAIL WITH M.C.R. WITNESS TAG IN SE FACE UTILITY POLE
N.41°W.	89.63'	SET PK NAIL WITH M.C.R. WITNESS TAG IN NE FACE UTILITY POLE

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

Signed by Steven E. Dunn Date Aug. 1, 1995
Surveyor's Michigan License No. 28408