

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|------------------------------|------------------------------|
| <u>MACOMB</u> (County) | Located in: <u>WARREN</u> | Corner Code # <u>I-13</u> |
| 1. Public Land Survey | <u>T 1N R 12E</u> | <u>I-13</u> |
| | <u>T R</u> | <u>_____</u> |
| | <u>T R</u> | <u>_____</u> |
| | <u>T R</u> | <u>_____</u> |
| 2. Property Controlling in Section | <u>S T R</u> | <u>_____</u> |
| | <u>S T R</u> | <u>_____</u> |
| 3. Miscellaneous Property in Sec. | <u>S T R</u> | <u>_____</u> |
| | <u>S T R</u> | <u>_____</u> |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

1091851
 LIBER 9268 PAGE 39
 12/27/1999 01:16:06 P.M.
 MACOMB COUNTY, MI
 CARMELLA SABAUGH, REG/DEEDS

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, STEVEN E. DUNN, in a field survey on August 16, 17, & 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH FLETCHER-1816

PLATS:

| | | |
|---------------------|--|--------------------|
| L.3, P.129 | Abbott & Beymer's Macomb Park Subd'n. | August 30, 1917 |
| L.3, P.151 | Frank C. Nail's Sun Set Hill Subd'n. | March 14, 1919 |
| L.3, P.183 | Abbott & Beymer's Victory Park Sub. | September 10, 1919 |
| L.8, P.54 | Mullin's Eight Mile Lawn Subdivision | November 14, 1924 |
| L.52, P.36 (W.C.R.) | Cummskey Park Subdivision | January 14, 1925 |
| L.9, P.70 | Arlington Manor | July 30, 1925 |
| L.60, P.32 (W.C.R.) | McGiverin-Haldeman's Seven Mile Drive Subd'n. No.1 | May 28, 1926 |

L.C.R.C.:

| | | | |
|---------------|----------------------------|---------------------------------|---------------|
| L.4665, P.608 | Robert J. Patterson #17631 | Found iron in center of 8 Mile. | June 15, 1989 |
|---------------|----------------------------|---------------------------------|---------------|

MDOT RAW Maps:

| | |
|--------------------------|----------------------|
| Macomb County-Sheets 6-8 | Rev. September, 1981 |
|--------------------------|----------------------|

CITY OF DETROIT CARTO MAPS-SHEET #93

October 12, 1953

MDOT PROJECT U397(4)-Eight Mile Road

September, 1956

CERTIFICATE OF SURVEY (unrecorded)

Nowak & Fraus Corp.

June 9, 1989

SKETCH OF SURVEY

Metco Dunn

June 16, 1994

BY THE MACOMB COUNTY SURVEY PEER
 AS THE OFFICIAL CORNER UNDER MICHIGAN
 ACT 345 OF 1990 AT A MEETING HELD
 10/12/99
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Section corner. Found 1/2" iron rod w/cap #30081 in centerline of grass median, 8.29' west of City of Detroit monument for I-1, T.1S., R.12E.

I verified the location of found 1/2" iron rod w/cap #30081 by comparing field measurements to record measurements of plats listed above and MDOT RAW maps.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

| | | | | |
|--|--|--|--|--|
| I-13 to H-13: GLO-40 Chains (2640.00') MDOT-2639.30' Field-2639.15' | I-13 to J-13: GLO-40 Chains (2640.00') MDOT-2649.40' Field-2650.07' | I-13 to I-1, T.1S., R.12E.: Sketch of Survey-8.33' Field-8.29' | ANGLE I-12/I-13/J-13: 89°29'15" MDOT 89°29'33" Field | SKETCH OF SURVEY: Set P.K. nail east face of U.P. Due South 17.23' (17.26' m.) Found cross on SW bolt on RRPost N.45°E. 46.25' (46.19' m.) |
|--|--|--|--|--|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I-13 SECTION CORNER

I REPLACED THE FOUND 1/2" IRON ROD WITH CAP #30081 WITH A CONCRETE MONUMENT WITH ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408".

WITNESSES:

- N.88°E. 8.29' Found concrete monument in monument box in grass median. I-1, T.1S., R.12E.
- S.3°E. 17.26' Found PK nail in east face of utility pole.
- S.54°W. 21.08' Found PK nail in north face of utility pole.
- S.46°E. 23.84' Found PK nail in southwest face of 7" tree.
- N.72°E. 46.19' Found "+" cut in top of southwest bolt railroad signal light.
- N.32°E. 108.38' Set Mag nail and Macomb County Remonumentation witness tag in west face of utility pole.



THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn

Date 12-2-99

Surveyor's Michigan License No. 28408

945