

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>MACOMB</u> (County)	Located In: <u>WARREN</u>	Corner Code # <u>          </u>
1. Public Land Survey	<u>T 1N R 12E</u>	<u>K-11</u>
	T <u>    </u> R <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
	T <u>    </u> R <u>    </u>	<u>          </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>          </u>
4. Lot No. <u>          </u> , Recorded Plat <u>          </u>		
5. Private Claims <u>          </u>		

1091852  
 LIBER 9268 PAGE 40  
 12/27/1999 01:16:06 P.M.  
 MACOMB COUNTY, MI  
 CARMELLA SABAUGH, REG/DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, STEVEN E. DUNN, in a field survey on August 18 & 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH WAMPLER-1817  
 PLATS:

L.6, P.12	Kaiser Gardens Subdivision	October 27, 1922
L.7, P.25	Blackett Little Farms Sub'n.	December 12, 1923
L.7, P.34	Hillside Sites Subdivision	January 18, 1924
L.7, P.56	Hitchman's Independence Park Subdivision	March 29, 1924
L.7, P.83	Abbott & Beymer's Half Way Gardens Subd'n.	June 19, 1924
L.8, P.15	Elm Park Subdivision	August 16, 1924
L.8, P.47	Heussner Garden Subdivision	October 20, 1924
L.9, P.19	Federal Park Subdivision	May 22, 1925
L.10, P.14	Elm Park Subdivision	September 8, 1925
L.11, P.3	Schmeman's-Groesbeck Boulevard Subd'n.	June 2, 1926
L.21, P.22	Supervisors Plat of East Detroit Little Farms Sub. and East Detroit Acres	October 25, 1941
L.23, P.22	Supervisor's Plat of Blackett Little Farms Sub. No. 1	December 21, 1945
L.45, P.45	Roger Subdivision	November 20, 1959

L.C.R.C.: L.5298, P.944 Raymond J. Donnelly #21563 Found 1/2" iron rod in monument box. January 13, 1992

MDOT R/W Maps: Macomb County-Sheet 73 Rev. September, 1981

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 K-11 Section corner common to Sections 26, 25, 35, & 36. Found 1/2" iron rod in monument box in asphalt capped concrete pavement. I verified the location of found 1/2" iron rod by comparing field measurements to record measurements of plats listed above and matching witness ties of above  
 L.C.R.C.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

K-11 to K-12: GLO-40 Chains (2640.00'). Plats-2625.25' east side. Plats-2623.43' west side. Field-2623.01'.	K-11 to L-11: GLO-40 Chains (2540.00'). Plats-2649.30' south side. Plats-2643.43' north side. Field-2643.80'	K-11 to J-11:(Not a remon corner) GLO-40 Chains (2640.00'). MDOT-2635.20'. Field-26	Angle L-11/K-11/K-12 Plat-90°50'00" Field-90°51'14"
---	--	--	---


L.C.R.C.:  
 Mag. AZ 59°, 57.80' (57.58' m.) to PK nail in NW face of utility pole.  
 Mag. AZ 126°, 59.96' (59.89' m.) to PK nail in NE face of utility pole.  
 Mag. AZ 231°, 62.85' (62.80' m.) to PK nail in SE face of utility pole.  
 Mag. AZ 319°, 65.01' (64.98' m.) to PK nail in SW face of utility pole.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 K-11 SECTION CORNER.

I REPLACED THE FOUND 1/2" IRON ROD WITH A 3/4" BY 24" IRON ROD WITH ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN EXISTING MONUMENT BOX.

WITNESSES:

- S.43°W. 62.80' Found nail and tag #21563 in southeast face of utility pole.
- S.37°W. 70.29' Center top nut of hydrant.
- N.49°W. 64.98' Found nail and tag #21563 in southwest face of utility pole.
- N.51°E. 57.58' Found nail and tag #21563 in southeast face of utility pole.
- S.61°E. 59.89' Found nail and tag # 21563 in northeast face of utility pole.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/12/99  
  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN



THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn Date 12-8-99  
 Surveyor's Michigan License No. 28408

984