

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MACOMB</u> (County)	Located In: <u>WARREN</u>	Corner Code # <u>K-12</u>
1. Public Land Survey	<u>T 1N R 12E</u>	<u>K-12</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1091853
 LIBER 9268 PAGE 41
 12/27/1999 01:16:06 P.M.
 MACOMB COUNTY, MI
 CARMELLA SABAUGH, REG/DEEDS

Register of Deeds Stamp & File Number

I, **STEVEN E. DUNN**, in a field survey on August 18, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5				4		3		2			
3													
4	7	8				9		10		11			12
5													
6	18	17				16		15		14			13
7													
8	19	20				21		22		23			24
9													
10	30	29				28		27		26			25
11													
12	31	32				33		34		35			36
13													

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH WAMPLER-1817

PLATS

L.6, P.6	National Gardens Subdivision	August 12, 1922
L.6, P.12	Kaiser Gardens Subdivision	October 27, 1922
L.6, P.24	Washington Gardens Subdivision	December 13, 1922
L.8, P.15	Elm Park Subdivision	August 16, 1924
L.8, P.47	Heussner Garden Subdivision	October 20, 1924
L.8, P.88	Rice & Miller's Subd'n.	March 18, 1925
L.9, P.19	Federal Park Sub'n.	May 22, 1925
L.10, P.14	Elm Park Subdivision No.1	September 8, 1925
L.10, P.55	John F. Keys Keyslawn Estates	March 9, 1926
L.38, P.4	Eastview Subdivision	November 5, 1956
L.45, P.45	Roger Subdivision	November 20, 1959

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 K-12 1/4 corner common to Sections 35 & 36. Found 3/4" iron rod in monument box in asphalt capped concrete pavement.

I verified the location of found 3/4" iron rod by comparing field measurements to record measurements of plats listed above.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

K-12 to K-11:	K-12 to K-13:
GLO-40 Chains (2640.00').	GLO-40 Chains (2640.00').
Plats-2625.25 East side.	Plats-2597.17' East side.
Plats-2623.43 West side.	Plats-2621.61' West side.
Field-2623.01'	Field-2621.03'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-12 1/4 Corner.

I PLACED AN ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" ON EXISTING 3/4" IRON ROD IN EXISTING MONUMENT BOX.

WITNESSES:

- S.49°E. 45.19' Set Mag nail and Macomb County witness tag in northeast face of utility pole.
- N.31°E. 60.11' Found PK nail and tag #19837 in southwest face of utility pole.
- N.68°E. 78.54' Center top nut of hydrant.
- N.54°W. 58.75' Found PK nail and Metco tag in northeast face of utility pole.
- S.39°W. 59.99' Found PK nail and tag #19837 in northeast face of utility pole.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/12/99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Signed by Steven E. Dunn Date 12-8-99

Surveyor's Michigan License No. 28408

185