

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MACOMB</u> (County)	Located In: <u>WARREN</u>	Corner Code # <u> </u>
1. Public Land Survey	<u>T 1N R 12E</u>	<u>K-13</u>
	<u>T R </u>	<u> </u>
	<u>T R </u>	<u> </u>
	<u>T R </u>	<u> </u>
2. Property Controlling in Section	<u>S T R</u>	<u> </u>
	<u>S T R</u>	<u> </u>
3. Miscellaneous Property in Sec.	<u>S T R</u>	<u> </u>
	<u>S T R</u>	<u> </u>

1091854
 LIBER 9268 PAGE 42
 12/27/1999 01:16:06 P.M.
 MACOMB COUNTY, MI
 CARMELLA SABAUGH, REG/DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, **STEVEN E. DUNN**, in a field survey on August 16 and 18, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

GLO POST-NO EVIDENCE OF ORIGINAL CORNER FOUND. GLO SURVEY PERFORMED BY JOSEPH FLETCHER-1816

PLATS:

L.6, P.6	National Gardens Subdivision
L.6, P.24	Washington Gardens Subdivision
L.6, P.88	Fairfield Gardens Subdivision
L.7, P.2	Eastwood Park Subd'n.
L.8, P.88	Rice & Miller's Subd'n.
L.54, P.55 (W.C.R.)	Waltham Manor Subdivision
L.54, P.98 (W.C.R.)	Schoenherr Manor Subdivision
L.55, P.8 (W.C.R.)	Hund's Regent Park Subdivision
L.9, P.70	Arlington Manor
L.10, P.55	John F. Keys Keystown Estates
L.59, P.88 (W.C.R.)	Drennan & Seldon's Regent Park Sub'n. No.3
L.19, P.36	Supervisor's Plat of Heath's Fairview Subdivision
L.21, P.41	Supervisor's Plat of Hillebrand Sub.
L.38, P.4	Eastview Subdivision

- August 12, 1922
- December 13, 1922
- July 26, 1923
- August 16, 1923
- March 18, 1925
- May 20, 1925
- June 2, 1925
- June 5, 1925
- July 30, 1925
- March 9, 1926
- April 30, 1926
- March 22, 1939
- January 21, 1942
- November 5, 1956



BY THE MACOMB COUNTY SURVEY PEER
 AS THE OFFICIAL CORNER UNDER MICHIGAN
 ACT 345 OF 1990 AT A MEETING HELD
 10/12/99
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

L.C.R.C.: L.29744, P.1031(W.C.R.)Martin C. Dunn #30081 Set Wayne County Remonumentation corner December 2, 1999

MDOT RW Maps: Macomb County-Sheets 8 & 9. Rev. September, 1981

CITY OF DETROIT CARTO MAPS Sheet No. 94 October 5, 1949

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 K-13 Section corner. Found boat spike in monument box in asphalt capped concrete pavement at centerline-centerline of 8 Mile Road and Schoenherr Road. Corner is common with K-1, Town 1 South, Range 12 East.

FIELD MEASUREMENTS & RECORD MEASUREMENTS:

K-13 to J-13: GLO-40 Chains (2640.00') Plats-2643.20' Wayne Co.-2643.30' Field-2642.48	K-13 to L-13: GLO-40 Chains (2640.00') Plats-2644.92' Field-2643.04'	K-13 to K-12: GLO-40 Chains (2640.00') Plats-2597.17' east side Plats-2621.61' west side Field-2621.03'	Angle J-13/K-13/K-12: Plat-90°19'30" Field-90°18'47"	L.C.R.C.: East 34.44' Set nail w/Wayne County Remon tag in north face U. P.(34.47'm.) West 53.25' Top north steel foundation bolt electric transmission tower.(53.20'm.)
--	---	---	--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-13 SECTION CORNER.

I ACCEPTED THE WAYNE COUNTY REMONUMENTATION CORNER WITH ALUMINUM CAP STAMPED #30081 IN EXISTING MONUMENT BOX.

WITNESSES:

- S.90°W. 53.20' Center top north steel foundation bolt electric transmission tower.
- S.28°W. 118.19' Found Mag nail and tag #23511.
- S.33°E. 112.05' Found City of Detroit Control Monument in handhole.
- N.87°E. 34.47' Found Mag nail and Wayne County Remonumentation witness tag in north face of utility pole.
- N.27°W. 114.84' Set Mag nail and Macomb County witness tag in northeast face of utility pole.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn Date 12-2-99

Surveyor's Michigan License No. 28408

986