

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MACOMB</u> (County)	Located In: <u>WARREN</u>	Corner Code # <u>M-7</u>
1. Public Land Survey	T <u>IN</u> R <u>12E</u>	<u>M-7</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

SURVEY & REMONUMENTATION

FEB 27 1997

COMMISSION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

STEVEN E. DUNN, in a field survey on AUGUST 7, 1996, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND ORIGINAL SURVEY PERFORMED BY PRESTON IN 1817

L.C.R.C.

L. 4650, P. 51 MARTIN C. DUNN #30081 FOUND CUT CROSS MAY 19, 1983

M.D.O.T.

RIGHT-OF-WAY MAPS/MACOMB CO.
 I-696 SHEET #26 JAN., 1978
 M-97 SHEET #76 APR., 1980

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7 SECTION CORNER COMMON TO A-7, T.1N., R.13E.
 FOUND CUT CROSS IN CONCRETE MEDIAN ON HAYES ROAD OVERPASS.
 MATCHED WITNESSES OF ABOVE L.C.R.C.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-20-96.

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

FIELD MEASUREMENTS AND RECORDED DISTANCES

L.C.R.C. NORTH	75.03'	CENTERLINE MONUMENT BOX EAST BOUND 11 MILE ROAD (75.03'M.)
WEST	41.85'	CURB LINE (41.85'M.)
EAST	42.18'	CURB LINE (42.18'M.)
M-7 TO M-6	2684.52'M. (2684.60' REC. R/W MAPS) 40 CHAINS (GLO 2640.00')	
M-7 TO L-7	2618.01'M. 40 CHAINS (GLO 2640.00')	
L-7/M-7/M-6	93°07'48" M. 93°07'26" REC. (R/W MAP-I-696)	

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 T.1N., R.12E.
 I REPLACED CUT CROSS WITH A WITH 1-1/8" DIAMETER BRASS MARKER STAMPED "MACOMB ACT 345" IN CONCRETE MEDIAN.

WITNESSES

NORTH	75.03'	FOUND CENTERLINE MONUMENT BOX IN WEST BOUND 11 MILE ROAD.
WEST	41.85'	FOUND FACE OF CONCRETE CURB.
EAST	42.18'	FOUND FACE OF CONCRETE CURB.
N.60°W.	53.36'	SET "+" ON TOP OF SE BOLT OF LIGHT POLE BASE.
S.53°E.	70.67'	SET "+" ON TOP OF NW BOLT OF LIGHT POLE BASE.
S.45°W.	70.85'	SET "+" ON TOP OF NE BOLT OF LIGHT POLE BASE.
SOUTH	239.42'	FOUND 1/2" IRON ROD IN MONUMENT BOX IN CENTERLINE OF EAST BOUND 11 MILE ROAD.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER

signed by Steven E. Dunn Date Nov. 12, 1996
 Surveyor's Michigan License No. 28408

