

SURVEY & MONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APR 07 1998

For corners in

MACOMB Located In: WARREN Corner Code # _____
 (County)

1. Public Land Survey T 1N R 12E M-8
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SECTION

C0623807 LIBER:07784 PAGE:384 08:57A 12/22/1997
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on OCTOBER 14, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND. ORIGINAL SURVEY PERFORMED BY WILLIAM PRESTON-1817

PLATS:

L. 9, P.12	HAYES BOULVARD SUBDIVISION	MAY 18, 1925
L. 18, P. 2	S.P. NO. 8	NOV. 4, 1936
L. 19, P. 19	S.P. OF LAMBRECHTS FARMS	JUN. 9, 1938

L.C.R.C.:

L. 3055, P. 812	ROBERT L. SMITH #16052	CUT "+" IN CONCRETE PAVEMENT	JAN. 15, 1979
-----------------	------------------------	------------------------------	---------------

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 FOUND "+" CUT IN CONCRETE PAVEMENT CORNER COMMON TO A - 8, T. 1N., R. 13E.
 I VERIFIED LOCATION OF FOUND "+" BY COMPARING FIELD MEASUREMENTS TO RECORD MEASUREMENTS OF FOUND CORNERS OF PLATS LISTED ABOVE. CORNER IS IN CENTERLINE INTERSECTION OF FRAZHO ROAD AND HAYES ROAD SOUTH AND 23.90' WEST OF CENTERLINE OF HAYES ROAD NORTH.

FIELD MEASUREMENTS AND RECORDED MEASUREMENTS:

M-8 TO M-7 (REMON CORNER)
 GLO-40 CHAINS OR 2640.00'
 FIELD - 2663.59'

M-8 TO M-9
 GLO - 40 CHAINS OR 2640.00'
 PLAT - 2679.20'
 FIELD- 2678.38'

ANGLE M-9/M-8/ CALCULATED E - W 1/4 LINE FROM CORNERS FOUND IN PLATS LISTED ABOVE
 PLATS - 86°23'00"
 FIELD - 86°23'57"

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11/18/97


William E. Soberberg
 WILLIAM E. SOBERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 T. 1N., R. 12 E.
 I REPLACED THE FOUND CUT + IN CONCRETE PAVEMENT WITH A 3/4" X 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN A NEW MONUMENT BOX.

WITNESSES:

N. 69°E.	56.80'	FOUND PK NAIL & TAG #19837 IN THE SOUTH FACE OF UTILITY POLE
S. 25°E.	47.85'	FOUND NAIL & MSHD TAG IN NE FACE OF UTILITY POLE
S. 25°E.	47.20'	FOUND NAIL & TAG (JOHNSON & ANDERSON) IN NORTH FACE UTILITY POLE
S. 58°W.	65.40'	FOUND NAIL & MSHD TAG IN SW FACE OF UTILITY POLE
N. 66°W.	54.00'	FOUND PK NAIL & TAG #19837 IN THE NE FACE OF UTILITY POLE
S. 58°W.	65.15'	FOUND NAIL AND TAG (JOHNSON & ANDERSON) IN SW FACE OF UTILITY POLE



THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn
 Surveyor's Michigan License No. 28408

Date Dec. 18, 1997

687