

**SURVEY &  
REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

FEB 27 1997

**COMMISSION**

For corners in

MACOMB

(County)

Located In:  
ERIN/LAKE

Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>1N</u> R <u>13E</u> | <u>A-7</u> |
|                                    | T ___ R ___              | _____      |
|                                    | T ___ R ___              | _____      |
|                                    | T ___ R ___              | _____      |
| 2. Property Controlling in Section | S ___ T ___ R ___        | _____      |
|                                    | S ___ T ___ R ___        | _____      |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___        | _____      |
|                                    | S ___ T ___ R ___        | _____      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEVEN E. DUNN, in a field survey on AUGUST 7, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

**GLO POST - NO EVIDENCE OF ORIGINAL CORNERS FOUND  
ORIGINAL SURVEY PREFORMED BY PRESTON IN 1817**

L.C.R.C.

L3168, P.950

ROBERT L. SMITH

#16052

FOUND "+" IN CONCRETE

OCT. 15, 1979

M.D.O.T.

RIGHT-OF-WAY MAPS/MACOMB CO.

I-696

SHEET #26

JAN., 1978

M-97

SHEET #76

APR., 1980

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 SECTION CORNER COMMON TO M-7, T.1N., R.12E.

FOUND CUT CROSS IN CONCRETE MEDIAN ON HAYES ROAD OVERPASS.  
MATCHED 2 OF 3 WITNESSES OF ABOVE L.C.R.C.

FIELD MEASUREMENTS AND RECORDED DISTANCES

L.C.R.C.	S.45°E.	70.68'	NW BOLT ON ST. LIGHT POLE (70.67'M.)
	N.45°W.	53.40'	SE BOLT ON ST. LIGHT POLE (53.36'M.)

A-7 TO A-6 2684.52'M. 2684.60' REC. (R/W MAPS) 40 CHAINS (GLO 2640.00')

WILLIAM E. SODERBERG, P.S., CHAIRMAN  
*William E. Soderberg*  
8/20/96  
NO  
PUBLIC ACT 345 OF 1990 AT A MEETING HELD  
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
ACCEPTED BY THE MACOMB COUNTY SURVEY BOARD

C0438541 LIBER:07245 PAGE:402 08:59A 11/14/1996  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 T.1N., R. 13 E.

I REPLACED CUT CROSS WITH A WITH 1-1/8" DIAMETER BRASS MARKER STAMPED " MACOMB ACT 345" IN CONCRETE MEDIAN.

WITNESSES

NORTH	75.03'	FOUND CENTERLINE MONUMENT BOX IN WEST BOUND 11 MILE ROAD.
WEST	41.85'	FOUND FACE OF CONCRETE CURB.
EAST	42.18'	FOUND FACE OF CONCRETE CURB.
N.60°W.	53.36'	SET "+" ON TOP OF SE BOLT OF LIGHT POLE BASE.
S.53°E.	70.67'	SET "+" ON TOP OF NW BOLT OF LIGHT POLE BASE.
S.45°W.	70.85'	SET "+" ON TOP OF NE BOLT OF LIGHT POLE BASE.
SOUTH	239.42'	FOUND 1/2" IRON ROD IN MONUMENT BOX IN CENTERLINE OF EAST BOUND 11 MILE ROAD.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE CORNER



Signed by Steven E. Dunn

Date Sep. 19, 1996

Surveyor's Michigan License No. 28408