

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb	Located In:	Corner Code #C8
(County)	Erin/Lake Township	
1. Public Land Survey	T <u>1N</u> R <u>13E</u>	<u>C8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Craig P. Amey, in a field survey on August 7, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1818 GLO	William Preston	No witnesses remain
1994 Unrecorded Survey	AEW	Set PK and tag #30092 at the intersection of Frazho and Groveland

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found PK and tag #30092 at the intersection of Frazho and Groveland
Witnesses from unrecorded survey


40°	50.66	PK with tag #30092 in the NW face of a 28" maple
150°	73.55	NW corner of porch at house #16802 Frazho Road
205°	69.64	SW corner of house #16758 Frazho Road
325°	89.35	NW corner of house #26201 Frazho Road

Corner was reestablished by determining the location of the section lines from the adjacent subdivisions and intersecting the section lines

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
REPLACED PK WITH 3/4" X 24" IRON WITH MCR CAP #34970 IN A NEW MONUMENT BOX

AZ 40°	50.66	PK with tag #30092 in the NW face of a 28" maple
AZ 150°	73.55	NW corner of porch at house #16802 Frazho Road
AZ 205°	69.64	SW corner of house #16758 Frazho Road
AZ 325°	89.35	NW corner of house #26201 Frazho Road

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.



ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-15-95
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Signed by *C. Amey*
Surveyor's Michigan License No. 34970

Date 12-12-95