

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

SURVEY &
REMONUMENTATION

APR 07 1998

MACOMB
(County)

Located In:
ERIN

Corner Code #

SECTION

1. Public Land Survey T 1N R 13E C-11
T ___ R ___
T ___ R ___
T ___ R ___
2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ I C0623804 LIBER:07784 PAGE:381 08:57A 12/22/1997
3. Miscellaneous S ___ T ___ I CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS
Property in Sec. S ___ T ___ R ___
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on OCTOBER 14, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND. ORIGINAL SURVEY PERFORMED BY WILLIAM PRESTON - 1817

PLATS:

- | | | |
|--------------|--------------------------------|----------------|
| L. 2, P. 230 | E.W. EYSTER SUB. | NOV. 21, 1914 |
| L. 3, P. 103 | LISCOMB PLAT | MAY 22, 1917 |
| L. 4, P. 7 | HALFWAY CITY | DEC. 01, 1919 |
| L. 4, P. 67 | PLEASANT RIDGE SUB. | MAY 26, 1920 |
| L. 4, P. 83 | KEY'S HALFWAY SMALL FARMS SUB. | JUN. 09, 1920 |
| L. 4, P. 101 | WILLIAM F. SCHULTZ SUB. | AUG. 18, 1920 |
| L. 5, P. 1 | MELROSE PARK SUB. | SEPT. 09, 1920 |
| L. 5, P. 3 | HALFWAY CITY SUB. NO. 1 | SEPT. 10, 1920 |
| L. 6, P. 68 | SCHUEREN AND MOK SUB. | JUN. 23, 1923 |
| L. 7, P. 12 | LONGACRES SUB. NO. 1 | SEPT. 12, 1923 |
| L. 10, P. 74 | CLARKS SUB. | MAY 22, 1926 |
| L. 22, P. 16 | A.P. #13 | MAY 16, 1942 |
| L. 37, P. 44 | CHUD & SOSKIN SUBD'N. NO. 1 | OCT. 02, 1956 |
| L. 38, P. 29 | A.P. #29 | JAN. 09, 1957 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
C-11 FOUND 1/2" IRON IN MONUMENT BOX IN CONCRETE PAVEMENT.

I VERIFIED LOCATION OF FOUND IRON BY COMPARING FIELD MEASUREMENTS TO RECORD MEASUREMENTS OF CORNERS FOUND IN ABOVE PLATS. CORNER IS AT SOUTH LINE OF LEFT TURN LANE OF 9 MILE ROAD AND 38.9' EAST OF CENTERLINE OF CUSHING ROAD.

FIELD MEASUREMENTS AND RECORD MEASUREMENTS:

- | | |
|-----------------------------|----------------------------|
| C-11 TO B-11 | C-11 TO C-12 |
| GLO - 40 CHAINS (2640.00') | GLO - 40 CHAINS (2640.00') |
| PLATS NORTH SIDE - 2725.78' | FIELD - 2661.94' |
| PLATS SOUTH SIDE - 2728.23' | |
| FIELD 2727.48' | |

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11/18/97


William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C.. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C - 11 T. 1N., R. 13E.
I REPLACED FOUND 1/2" IRON ROD WITH A 3/4" X 24" IRON ROD WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345" #28408 IN EXISTING MONUMENT BOX.

WITNESSES:

- | | |
|-----------------|--|
| NORTH 38.43' | SET MAG NAIL & MCR WITNESS TAG IN WEST FACE OF UTILITY POLE. |
| SOUTH 28.10' | SET MAG NAIL & MCR WITNESS TAG IN EAST FACE OF UTILITY POLE. |
| S. 76°W. 73.80' | NE CORNER OF CATCH BASIN CASTING. |
| N. 61°W. 79.55' | SE CORNER OF CATCH BASIN CASTING. |



THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE ORIGINAL CORNER.

Signed by *Steven E. Dunn*
Surveyor's Michigan License No. 28408

Date *Dec. 10, 1997*

684