

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

C152284

94 DEC 14 AM 10:55

MACOMB COUNTY
REGISTERED
DEEDS CITY, MT

LIBER 6527 PAGE 861

Register of Deeds Stamp & File Number

MACOMB

(County)

Located In:
ERIN/LAKE

Corner Code #

Public Land Survey

T 1N R 13E

E-1

Property Controlling
in Section

S T R

Miscellaneous

S T R

Property in Sec.

S T R

Lot No. _____, Recorded Plat _____

Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11				12
5													
6	16		17		18		15		14				13
7													
8	19		20		21		22		23				24
9													
10	30		29		28		27		26				25
11													
12	31		32		33		34		35				36
13													

STEVEN E. DUNN, in a field survey on MARCH 20, 19 94,
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore
required in the current manual of survey instructions of the United States Department of
the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the
corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the
Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be
recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY

L.C.R.C. E-1, T.1N., R.13E.

L. 3551 P. 378 WILLIAM E. SODERBERG, #17635 FOUND 1/4" PIPE IN MONUMENT BOX

OCTOBER 13, 1983

PLAT

L. 03 P. 161 HARMON FARMS JULY 26, 1919
L. 17 P. 030 SUPERVISOR'S PLAT NO. 2 JULY 21, 1936

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 SECTION CORNER COMMON TO E-13 CLINTON TOWNSHIP

FOUND 1/2" IRON ROD IN MONUMENT BOX IN CONCRETE PAVEMENT
VERIFIED LOCATION BY COMPARING FOUND WITNESSES OF L.C.R.C. LISTED BELOW AND DISTANCE
FROM E-13 TO D-13 AS SHOWN ON SUPERVISOR'S PLAT NO. 2 LISTED ABOVE AND ON MDOT RAW
MAP, MACOMB COUNTY, SHEET 79. ALSO COMPARED DISTANCE FROM E-13 TO F-13 AS
SHOWN ON PLAT HARMON FARMS LISTED ABOVE.

FOUND WITNESS TIES

L. 3551 P. 378 S.45°E. 123.63' NORTHWEST CORNER BRICK APARTMENT BUILDING
N.40°E. 140.76' SOUTHWEST CORNER BRICK BUILDING

FIELD MEASUREMENTS AND RECORDED DISTANCES

E-1 TO D-1 2703.12' (M.) 2640.00' G.L.O. (R.)
E-1 TO F-1 2699.14' (M.) 2640.00' G.L.O. (R.)

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**E-1 T.1N., R.13E. I REPLACED 1/2" IRON ROD WITH A 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP
STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408 IN AN EXISTING MONUMENT BOX.**

WITNESSES

S.48°W. 67.49' LIGHT POLE
N.43°W. 64.09' PK NAIL IN UTILITY POLE
N.44°E 140.74' SOUTHWEST CORNER OF BRICK BUILDING
S.41°E. 123.45' NORTHWEST CORNER OF BRICK APARTMENT BUILDING
S.33°E. 56.82' PK NAIL IN UTILITY POLE

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990 AT A MEETING HELD
ON 10-4-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE
EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

signed by Steven E. Dunn Date Nov. 9, 1994

Surveyor's Michigan License No. 28408