

# SURVEY & REMONUMENTATION


APR 29 1996

## COMMISSION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb Located In: Erin/Lake Township Corner Code #E8  
(County)

- |                                    |       |                          |  |           |
|------------------------------------|-------|--------------------------|--|-----------|
| 1. Public Land Survey              |       | T <u>1N</u> R <u>13E</u> |  | <u>E8</u> |
|                                    |       | T ___ R ___              |  | _____     |
|                                    |       | T ___ R ___              |  | _____     |
|                                    |       | T ___ R ___              |  | _____     |
| 2. Property Controlling in Section | S ___ | T ___ R ___              |  | _____     |
|                                    | S ___ | T ___ R ___              |  | _____     |
| 3. Miscellaneous Property in Sec.  | S ___ | T ___ R ___              |  | _____     |
|                                    | S ___ | T ___ R ___              |  | _____     |



4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Craig P. Amey, in a field survey on August 8, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**


	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1818 GLO Wooden post William Preston No witnesses remain

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found PK at the intersection of the centerlines of Kelly Avenue and Frazho Road.  
Corner verified by:  
Matched tie distances to a monument at the southeast corner of Huron Street and Frazho Road, part of "Catlin Sub'n" as recorded in Liber 36, Page 19.  
Matched tie distances to a monument at the northeasterly corner of "Salem Park Subd'n" as recorded in Liber 28, Page 19.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET A 3/4" X 24" IRON WITH MCR CAP #34970 IN A NEW MONUMENT BOX
- AZ 320° 76.60' PK and tag #30092 in the northeast face of a 14" Box Elder
- AZ 15° 58.38' PK and tag #30092 in the north face of a 14" Maple
- AZ 130° 116.50' Northwesterly corner of wall at building #25990 Kelly Road
- AZ 215° 75.00' Northeast corner of building at north end of brick on the east wall of building #18340 Kelly Rd

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-15-95  
*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Signed by *C. Amey* Date 12-12-95  
Surveyor's Michigan License No. 34970

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1983