

SURVEY & REMONUMENTATION

APR 29 1996

LAND CORNER RECORDATION CERTIFICATE COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb Located In: Erin/Lake Township Corner Code #G3
(County)

- | | | |
|------------------------------------|--------------------------|-----------|
| 1. Public Land Survey | T <u>1N</u> R <u>13E</u> | <u>G3</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Craig P. Amey, in a field survey on August 7, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3							●						
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1818 GLO	William Preston	No witnesses remain
1983 LCRC	L3551 P371 William E. Soderberg	Found boat spike in mon box at 13 Mile and Little Mack

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found boat spike in a monument box at the intersection of 13 Mile and Little Mack (Concrete)

This corner verified by:

Witnesses from LCRC, L3551 P371

N56E	81.21	PK Nail in the SE side of a utility pole
S36W	61.33	PK and shiner in the NE side of a utility pole
N37W	57.55	PK and shiner in the SE side of a utility pole

W	2699.58'	South quarter post of section 4 (F3)
S	2696.39'	East quarter post of section 9 (G4)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED BOAT SPIKE WITH 3/4" X 24" IRON WITH MCR CAP #34970 IN THE EXISTING MONUMENT BOX

AZ	130°	73.07	PK and MCR tag in the SW face of a utility pole
AZ	220°	61.80	PK and GW tag in the NW face of a utility pole
AZ	320°	58.52	PK and GW tag in the SW face of a utility pole
AZ	60°	81.10	PK and GW tag in the SE face of a utility pole

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-15-95
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Signed by C. Amey Date 12-15-95

Surveyor's Michigan License No. 34970

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN, 1983