

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSIONER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb Located In: Erin/Lake Township Corner Code #G4
(County)

1. Public Land Survey		<u>T 1N R 13E</u>	<u>G4</u>
		T ___ R ___	_____
		T ___ R ___	_____
		T ___ R ___	_____
2. Property Controlling in Section	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___	T ___ R ___	_____
	S ___	T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Craig P. Amey, in a field survey on August 7, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1818 GLO		William Preston	No witnesses remain
1983 LCRC	L3551 P371	William E. Soderberg	Found rered in mon box in centerline of Little Mack

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found rered in a monument box in the centerline of Little Mack Road (Concrete)

This corner verified by:

Witnesses from LCRC, L3551 P371

N72E	35.00	NW corner of a catch basin
N11W	118.72	PK in the E side of a utility pole

S	2683.22'	Southeast corner of section 9 (G5) (GLO = 40ch)
N	2696.39'	Northeast corner of section 9 (G3) (GLO = 40ch)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED REROD WITH 3/4" X 24" IRON WITH MCR CAP #34970 IN THE EXISTING MONUMENT BOX

140°	90.76	SW corner of a concrete porch at Clancy's Trucking
270°	34.05	Set PK and MCR tag in the S face of a utility pole
345°	118.65	Set PK and MCR tag in the E face of a utility pole
72°	35.00	NW corner of a catch basin

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990 AT A MEETING HELD
ON 8-15-95
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Signed by *C. Amey* Date 12-15-95
Surveyor's Michigan License No. 34970

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

C0292271 LIBER:06862 PAGE:830 11:11A 12/21/1995
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

REVISED MAY 14, 1975
REVISED JAN., 1983