

# SURVEY & REMONUMENTATION

APR 29 1996

## LAND CORNER RECORDATION CERTIFICATE COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb	Located In:	Corner Code #G8
(County)	Erin/Lake Township	
1. Public Land Survey	T <u>1N</u> R <u>13E</u>	<u>G8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Craig P. Amey, in a field survey on August 8, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1818 GLO William Preston No witnesses remain

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found PK nail in the intersection of the physical centerlines of Little Mack Road and Frazho Road  
This corner verified by:

"Lakewood Gardens No. 3", as recorded in Liber 8, Page 33, Macomb County Records.  
The east line of this subdivision extends from the southeast corner of section 21 (G9) to the west quarter post of section 21 (G8). The record distance is 2694.62 feet and the measured distance is 2697.51 feet..

"Coussement Subdivision", as recorded in Liber 38, Page 37, Macomb County Records.  
The record angle subtended by Frazho Road and Little Mack Road is 89°50'00". The measured angle is 89°47'04"

"Lakewood Gardens No. 3", as recorded in Liber 8, Page 33, Macomb County Records.  
The record angle subtended by Frazho Road and Little Mack Road is 89°44'. The measured angle is 89°51'36"

N 2696.75 Northeast corner of section 21 (G7) (GLO = 40ch)  
S 2694.51 Southeast corner of section 21 (G9) (GLO = 40ch)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
REPLACED PK WITH 3/4" X 24" IRON WITH MCR CAP #34970 IN A NEW MONUMENT BOX

AZ	133°	39.03	Set PK nail and CPA tag in the southwest face of a utility pole
AZ	58°	43.85	Set PK nail and CPA tag in the south side of a 22" maple
AZ	310°	61.31	Found PK nail and MSHD tag in the north face of a utility pole
AZ	262°	72.58	Chiseled "X" in the north rim of a catch basin

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-15-95  
*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN



Signed by *C. Amey* Date 12-15-95

Surveyor's Michigan License No. 34970

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1983