

**SURVEY & REMONUMENTATION**

APR 29 1996

C0257447 LIBER:06779 PAGE:621 03:43P 10/03/1995  
 CARMELLA SABAUGH--MACOMB COUNTY, MI REG/DEEDS

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**COMMISSION**

For corners in

<u>MACOMB</u> (County)	Located in: Sterling Township	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>12E</u>	<u>A-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Randy Kolehouse, in a field survey on June 21 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

A-3	Records indicate this corner is common with T2N R11E.			
1817	G.L.O. Notes	Wampler (T2N R11E)	N/A	Set Post
1928	M.C.R.C. Files	N/A	N/A	Found Std. Mon. Box
1973	L.C.R.C. L. 2380 P. 494	Patterson	#17631	Found Iron in Hand Hole
1973	Cert. Survey L. 2303 P. 188	Avey	#15396	Found 1/2" Pipe in Mon. Box
1974	Cert. Survey L. 2556 P. 568	Smith	N/A	Found 1/2" Iron in Mon. Box
1977	L.C.R.C. L. 2886 P. 441	Patterson	#17631	Found 1/2" Iron in Mon. Box
1989	L.C.R.C. L. 4606 P. 102	Patterson	#17631	Found 1/2" Iron in Mon. Box
1989	L.C.R.C. L. 4608 P. 38	Bailey	#33968	Found 1/2" Iron in Mon. Box

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

A-3 Found 1" iron pipe in monument box at the center line intersection of Dequindre Road and 19 Mile Road. This point checks the following witnesses.

- L.C.R.C. L. 4606 P. 102 Nail & tag in utility pole Southwesterly 72.70'
- L.C.R.C. L. 2886 P. 441 Found nail & washer in utility pole NW'ly 82.32'
- L.C.R.C. L. 2303 P. 188 82.70' W.N.W. to 16d conc. nail in N. face p. pole
- L.C.R.C. L. 2380 P. 494 P.K. Nail in utility pole N.W.'ly 82.05'
- L.C.R.C. L. 4608 P. 38 S30°E 122.74 P.K. Nail and Washer in West face of utility pole
- S 38°W 72.60 ft. Nail and Washer in S.E. face of utility pole
- N60°W 82.47 ft. Nail and Washer in N.E. face of utility pole

Measure South 2653.44 to A-4 (Forest Brook Sub. = 2653.55) (G.L.O. 2640.0)  
 Measure North 2649.92 to A-2 (G.L.O. 2640.0)  
 Measure East 2734.43 to B-3 (Brookside Sub = 2734.65) (Forest Brook Sub. = 2734.65) (G.L.O. 2608.3)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8/15/95

*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

A-3 I replaced the found 1" iron pipe with a 3/4" x 24" iron rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854" in an existing monument box.

- Nail and Macomb Co. Remon. Tag in N Face P. Pole S 30° E 67.99'
- Nail and Macomb Co. Remon. Tag in E Face P. Pole S 50° W 70.99'
- Nail and Macomb Co. Remon. Tag in N Face P. Pole N 60° W 82.38'
- Nail and Macomb Co. Remon. Tag in N Face P. Pole N 65° E 58.88'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 8/14/95  
 Surveyor's Michigan License No. 25854

