

SURVEY & REMONUMENTATION

APR 29 1996

COMMISSION

C0257449 LIBER:06779 PAGE:623 03:43P 10/03/1995
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MACOMB</u> (County)	Located in: Sterling Township	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>12E</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

ACCEPTED BY THE MACOMB COUNTY SURVEY PEEF GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8/15/95

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on June 21 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-5	Records indicate this corner is common with T2N R11E.			
1817	G.L.O. Notes	Wampler (T2N R11E)	N/A	Set Post
1928	M.C.R.C. Files	N/A	N/A	Found Axle in Mon. Box
1949	M.C.R.C. Files	N/A	N/A	3/4" Solid Iron
1973	L.C.R.C. L. 2380 P. 492	Patterson	#17631	Iron in Hand Hole
1973	Cert. Survey L. 2453 P. 40	Carlson	#14759	Found 2" Iron in Hand Hole
1973	L.C.R.C. L. 2453 P. 42	Carlson	#14759	Found 2" Iron in Hand Hole
1993	L.C.R.C. L. 5775 P. 921	Van Havermaat	#33988	Found 1 1/4" Iron in Mon. Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5 Found 1 1/4" iron in monument box at center line of 18 Mile Road and Dequindre Road which checks Ambere Point Subdivision and agrees with the following witnesses.

L.C.R.C. L. 2453 P. 42	L.C.R.C. L. 5775 P. 921
N. 43° W 68.60 ft. to D.E. pole	Az 46 degrees 61.30 feet P.K. nail in SW face of Util. Pole
S. 45° W. 64.70 ft. to P.K. nail in M.B.T. pole	Az 121 degrees 66.00 feet P.K. nail in NW face of Util. Pole
S. 51° E. 66.40 ft. to pole	Az 205 degrees 63.25 feet P.K. nail in NE face of Light Pole
	Az 309 degrees 68.60 feet P.K. nail in SE face of Util. Pole

Measure S 2660.12 to A-6 (G.L.O. 2640.0)
 Measure N 2622.95 to A-4 (Ambere Pointe Sub. = 2622.95) (G.L.O. 2640.0)
 Measure E 2655.7 to B-5 (G.L.O. 2655.84)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5 I replaced the found 1 1/4" iron with a 3/4" x 24" iron rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854" in an existing monument box.

- Nail and Macomb Co. Remon. Tag in SW Face P. Pole S 20° E 79.94'
- Nail and Macomb Co. Remon. Tag in SE Face P. Pole S 20° W 69.73'
- NE Cor. Brick Bldg. N 30° W 255.03'
- Nail and Macomb Co. Remon. Tag in NW Face P. Pole N 45° E 69.04'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 9/14/95
 Surveyor's Michigan License No. 25854

