

**SURVEY & REMONUMENTATION**

APR 29 1996

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)	Located in: Sterling Township	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>12E</u>	<u>A-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on June 21 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-6	Records indicate this corner is common with T2N R11E.				
1817	G.L.O. Notes	Wampler (T2N R11E)	N/A	Set Post	
1972	Cert. Survey L. 2358 P. 928	Cantrell	#5782	P.K. in Hand Hole	
1973	L.C.R.C. L. 2358 P. 932	Cantrell	#5782	Found Hand Hole	

C0257450 LIBER:06779 PAGE:624 03:43P 10/03/1995  
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6 Hand hole has been destroyed. I reestablished corner using Cert. Survey L. 2358 P. 930. This point checks two remaining witnesses from Cert. Survey L. 2358 P. 928 and 930.

D.E. Pole NE 67.0'  
 D.E. Pole SE 114.5'

Measure S 2644.3 to A-7 (G.L.O. 2640.0)  
 Measure N 2660.12 to A-5 (G.L.O. 2640.0)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8/15/95

*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6 Set a 5/8" iron w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854." Also set a new monument box.

- Nail and Macomb Co. Remon. Tag in N Face P. Pole N 50° E 67.00'
- Nail and Macomb Co. Remon. Tag in N Face P. Pole S 20° E 114.43'
- NE Cor. Brick Bldg. 246.56'
- Nail and Macomb Co. Remon. Tag in Bit. at SW Cor. of Drive Ent. 0.5' ± E of Face at Walk 55.42'
- C/L Hyd. N 70° E 54.32'
- C/L Hyd. N 30° W 65.99'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J Kolehouse Date 9/4/95  
 Surveyor's Michigan License No. 25854

