

# SURVEY & REMONUMENTATION

APR 29 1996

C0257451 LIBER:06779 PAGE:625 03:43P 10/03/1995  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

## COMMISSION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB <small>(County)</small>	Located in: Sterling Township	Corner Code #	
1. Public Land Survey	T <u>2N</u> R <u>12E</u>	<u>A-7</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on June 20 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-7 Records indicate this corner is common with T2N R11E.

1817	G.L.O. Notes	Wampler (T2N R11E)	N/A	Set Post
1972	L.C.R.C. L. 2371 P. 783	Avendt	#16034	Fnd. Mon. Box (No Iron or Pipe)
1973	L.C.R.C. L. 2358 P. 932	Cantrell	#5782	Fnd. Mon. Box (No Iron or Pipe)
1973	Cert. Survey L. 2358 P. 930	Cantrell	#5782	Fnd. Mon. Box (No Iron or Pipe)
1973	Cert. Survey L. 2371 P. 773	Avendt	#16034	Fnd. Mon. Box (No Iron or Pipe)
1993	Sterling Heights Road Plans	Hubbell, Roth & Clark		Iron in Mon. Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7 Found 5/8" rebar in monument box at center line intersection of 17 Mile Road and Dequindre Road which checks Road Alignment Plans from the City of Sterling Heights prepared by Hubbell, Roth & Clark. All other witnesses have been destroyed.

Road Plans  
P.K. in Utl. Pole N 17° E 138.98'  
P.K. in Utl. Pole S 79° W 201.18'

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER  
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990 AT A MEETING HELD  
ON 8/19/95

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Measure East 2492.75 to B-7 (Arlingdale Heights Sub. = 2493.22) (Road Plans = 2492.8) (G.L.O. 2682.24)  
Measure North 2644.41 to A-6 (G.L.O. 2640.0)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 I replaced the found 5/8" rebar with a 3/4" x 24" iron rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854" in an existing monument box.

- Nail and Macomb Co. Remon. Tag in E Face P. Pole N 25° W 60.84'
- Nail and Macomb Co. Remon. Tag in N Face P. Pole S 70° W 64.91'
- Nail and Macomb Co. Remon. Tag in N Face P. Pole S 30° E 66.07'
- Nail and Macomb Co. Remon. Tag in S Face P. Pole N 60° E 72.44'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by *Randy J. Kolehouse* Date 9/4/95  
Surveyor's Michigan License No. 25854

