

**SURVEY & REMONUMENTATION**

APR 29 1996

C0257452 LIBER:06779 PAGE:626 03:43P 10/03/1995  
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)	Located in: Sterling Township	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>12E</u>	<u>B-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

ACCEPTED BY THE MACOMB COUNTY SURVEY PEEF  
 GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD  
 ON 8/15/95

*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on June 20 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-3	1817	G.L.O. Notes	Wampler	N/A	Set Post
	1973	L.C.R.C. L. 2380 P. 494	Patterson	#17631	Iron in Gravel Road
	1977	L.C.R.C. L. 2886 P. 441	Patterson	#17631	Fnd. P.K. - Mon. Box 0.70' SE
	1977	L.C.R.C. L. 2765 P. 340	Pawiaczyk	#17632	Found Mon. Box
	1977	Cert. Survey L. 2765 P. 339	Giffeis-Webster	#17632	Found Mon. Box
	1985	L.C.R.C. L. 3884 P. 70	Fenn	#23505	Found 1" Steel Rod in Mon. Box
	1989	L.C.R.C. L. 4608 P. 37	Bailey	#33968	Found 1" Steel Rod in Mon. Box
	1990	L.C.R.C. L. 4854 P. 208	Patterson	#17631	Found Iron in Mon. Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-3 Found 1/2" Rebar in monument box in the center line of 19 Mile Road which checks with Forest Brook Sub. and Brookside Sub. and agrees with the following witnesses.

L.C.R.C. L. 4854 P. 208  
 N. 70°W. 122.50 ft. - P.K. in U.P. N. 50°E. 56.23 ft.

L.C.R.C. L. 3884 P. 70  
 N.E. 56.95 found G&W tag #6870 in South face utility pole  
 N.W. 122.45 found P.K. nail in South face utility pole

L.C.R.C. L. 4608 P. 37  
 N50°E 56.84 ft. Found G/W/E Tag in S.E. face of utility pole  
 N72°W 122.06 ft. Found P.K. Nail in S.E. face of utility pole

L.C.R.C. L. 2886 P. 441  
 GW nail & washer in utility pole NE'y 56.99 ft.  
 Set PK nail in utility pole NW'y 121.90 ft.

Measure W 2734.43 to A-3 (Brookside Sub. = 2734.65) (Forest Brook Sub. = 2734.65) (G.L.O. 2608.3)  
 Measure E 2485.19 to C-3 (Brookside Sub. = 2485.23) (Forest Brook Sub. = 2485.23) (G.L.O. 2640.0)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3 I replaced the found 1/2" rebar with a 3/4" x 24" iron rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854" in an existing monument box.

- Nail and Macomb Co. Remon. Tag in SE Side P. Pole N 60° E 56.68'
- Nail and Macomb Co. Remon. Tag in N Side P. Pole N 70° W 122.42'
- Nail and Macomb Co. Remon. Tag in SE Side P. Pole S 77° W 130.78'
- Concrete Monument N 05° E 60.47'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J. Kolehouse Date 9/14/95  
 Surveyor's Michigan License No. 25854

