

APR 29 1996

C0257453 LIBER:06779 PAGE:627 03:43P 10/03/1995  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)	Located in: Sterling Township	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>12E</u>	<u>B-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8/11/95

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on June 20 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-5	1817	G.L.O. Notes	Wampler	N/A	Set Post
	1960	M.C.R.C. File	N/A	N/A	3/4" Pipe
	1973	Cert. Survey L. 2453 P. 40	Carlson	#33597	Fnd. P.K. Nail
	1973	L.C.R.C. L. 2380 P. 492	Patterson	#17631	Fnd. P.K. Nail in Asphalt
	1977	L.C.R.C. L. 2886 P. 439	Patterson	#17631	Fnd. 1/2" Iron Pipe
	1989	L.C.R.C. L. 4723 P. 606	Donnelly	#21563	Fnd 1/2" Iron Rod in Mon. Box
	1993	L.C.R.C. L. 5775 P. 921	Van Havermaat	#33988	Fnd. 1/2" Iron Rod in Mon. Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5 Found boat spike in monument box on the center line of 18 Mile Road pavement running E-W and on fence line running South which checks Villager Sub. No. 2 & Pine Brook Sub. and the following witnesses.

L.C.R.C. L. 2380 P. 492 P.K. Nail in utility pole S.E.'ly 122.35 ft.	L.C.R.C. L. 4723 P. 606 Az 120 degrees 66.81 feet P.K. nail in North face of 14" tree Az 197 degrees 29.00 feet P.K. nail with R.J.D. flasher in East face of U. Pole
---	---

L.C.R.C. L. 2886 P. 439 P.K. nail in utility pole SE'ly 122.27 ft.	L.C.R.C. L. 5775 P. 921 Az 120 degrees 66.81 feet P.K. nail in North face of 14" tree Az 197 degrees 29.00 feet P.K. nail with R.J.D. washer in East face of util pole Az 287 degrees 132.15 feet P.K. nail in guy pole
---	--

Measure E 2479.74 to C-5 (Villager Sub. No. 2 = 2479.59) ( G.L.O. 2640.0)  
Measure W 2655.70 to A-5 (Pine Brook Sub. = 2655.50) (G.L.O. 2655.84)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5 I replaced the found boat spike with a 3/4" x 24" iron rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854" in an existing monument box.

- Nail and Macomb Co. Remon. Tag in E Side P. Pole S 18° W 28.99'
- Nail and Macomb Co. Remon. Tag in S Side Guy Pole N 70° W 132.01'
- Nail and Macomb Co. Remon. Tag in SW Side P. Pole S 72° E 122.60'
- Nail and Macomb Co. Remon. Tag in NE Side 14" Ash S 60° E 66.79'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Randy J Kolehouse Date 9/14/95  
Surveyor's Michigan License No. 25854

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

