

APR 29 1996

COMMISSION

C0257459 LIBER:06779 PAGE:633 03:43P 10/03/1995
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)	Located in: Sterling Township	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>12E</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randy Kolehouse, in a field survey on June 20 19 95, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5	1817	G.L.O. Notes	Wampler	N/A	Set Post
	N/A	M.C.R.C. File 62	N/A	N/A	1/4" Iron
	N/A	M.C.R.C. File 62	N/A	N/A	3/4" Solid Iron
	1977	L.C.R.C. L. 2886 P. 439	Patterson	#1763	1/2" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 Found a 1/2" iron pipe on the center line of 18 Mile Road running East & West which checks the following witness.

L.C.R.C. L. 2886 P. 439
Set PK nail in utility pole SW'ly 94.77 ft.

Measure E 2649.45 to E-5 (G.L.O. 2640.0)
Measure W 2803.44 to C-5 (Spice Mill Sub. No. 2 = 2803.7) (G.L.O. 2640.0)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8/15/95


William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 I replaced the found 1/2" iron with a 3/4" x 24" iron rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854." Also set a new monument box.

- Nail and Macomb Co. Remon. Tag in SE Side P. Pole S 75° W 94.69'
- Nail and Macomb Co. Remon. Tag in E Side 12" Maple S 15° W 62.89'
- Nail and Macomb Co. Remon. Tag in NE Side P. Pole S 62° E 78.73'
- Concrete Plat Monument N 75° E 155.39'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.



Signed by Randy J. Kolehouse Date 9/5/95
Surveyor's Michigan License No. 25854