

SURVEY & REMONUMENTATION

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

C152250

COMMISSION

or corners in
MACOMB
(County)

Located In: Sterling Township Corner Code #

Public Land Survey	T	2N	R	12E	F-7
	T		R		
	T		R		
	T		R		
Property Controlling in Section	S		T		R
Miscellaneous	S		T		R
Property in Sec.	S		T		R

94 DEC 14 AM 10:53
MICHIGAN REGISTER OF DEEDS
MACOMB COUNTY, MI

LIBER 6527 PAGE 827

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

Randy Kolehouse, in a field survey on August 1, 1994,
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

-7	1817	G.L.O.	Notes	Wampler	NA	Post
	1978	L.C.R.C.	L. 2936 P. 222	Hooth	#7966	"T" Iron in Mon. Box
	1980	Survey	L. 3281 P. 839	Merdzinski	#10697	
	1980	Survey	L. 3292 P. 783	Merdzinski	#10697	
		MCRC	File #86	NA	NA	Reinforcing Rod

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

-7 Found 5/8" rebar in monument box in bridge deck and hub and tack below in ground surface. Checks same location.

L.C.R.C. L. 2936 P. 222
Power Pole N 10° W 64.35'

MCRC
SE Corner Post of Fence NW 74.5'
Center Line West Rail E 23.55'

L.C.R.C. L. 3281 P. 839
Power Pole N 10° W 64.35'

Measure 2641.89 W to E-7 (G.L.O. = 2647.26)
Measure 2685.93 E to G-7 (WW 2686.08) (G.L.O. 2647.26)


ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-20-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-7 I replaced the found Hub & Tack with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854."

- *+ SW Bolt Lt. Pole Base N 51° W 78.26'
- *+ NE Bolt Lt. Pole Base S 40° E 67.62'
- *+ Center Line Top Bolt on Hyd. S 60° E 163.41'
- *+ Top of Wall at Dedication Plaque N 81° E 78.84'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.



Surveyed by Randy J. Kolehouse
Surveyor's Michigan License No. 25854

Date 10/14/94