

# SURVEY & REMONUMENTATION

C152252

APR 28 1995

## LAND CORNER RECORDATION CERTIFICATE

94 DEC 14 AM 10:54

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB

(County)

Located In: Sterling Township Corner Code #

Public Land Survey	T <u>2N</u>	R <u>12E</u>	_____	G-4	_____
	T _____	R _____	_____	_____	_____
	T _____	R _____	_____	_____	_____
	T _____	R _____	_____	_____	_____
Property Controlling in Section	S _____	T _____	R _____	_____	_____
Miscellaneous Property in Sec.	S _____	T _____	R _____	_____	_____

STATE OF MICHIGAN  
REGISTER OF DEEDS  
MACOMB COUNTY, MI

LIBER **6527** PAGE **829**

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Randy Kolehouse, in a field survey on June 28, 19 94,  
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

1-4	1817	G.L.O.	Notes	Wampler	NA	Post
	1975	Survey	L. 2564 P. 447	Avey	#15396	1/2" Bar in Mon. Box
	1990	L.C.R.C.	L. 04852 P. 258	Fenn	#23505	1/2" Iron Bar in Mon. Box
		Survey	L. 85 P. 10	Fraus	#17089	NA

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

4 Found 1/2" rebar in monument box in center line Van Dyke Road and 18-1/2 Mile Road

Survey L. 2564 P. 447	L.C.R.C. L. 4852 P. 258
PK N Face Util. Pole E 58.98'	PK and Fenn Tag S Face Util. Pole NW 66.19
PK S Face Lt. Pole WNW 66.24'	PK and Fenn Tag E Face Util. Pole NNW 114.90'
	PK and Tag N Face Util. Pole ENE 58.63'
	PK and Tag W Face Util. Pole SE 152.49'

Measure N. 2701.14 to G-3 (Survey L. 2564 P. 447 = 2700.99) (G.L.O. 2640)  
Measure S. 2552.68 to G-5 (G.L.O. 2640)

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4 I replaced the found 1/2" Rebar with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25854" in an existing Monument Box.

- PK with Tag #23505 E Face Util. Pole N 12° W 114.90'
- PK with Tag #23505 S Face Lt. Pole N 64° W 66.20'
- PK with Tag W Face P. Pole S 14° E 267.29'
- PK with Tag N Face P. Pole N 71° E 58.63'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Surveyed by Randy J. Kolehouse Date 10/14/94  
Surveyor's Michigan License No. 25854

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-16-94  
*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

