

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MACOMB</u> (County)	Located in:	City of Sterling Heights	Corner Code # G-10
1. Public Land Survey	T <u>2N</u>	R <u>12E</u>	<u>G-10</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

REGISTERED
 REGISTERED

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Bruce Antcliff, in a field survey on September 3 19 98, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-10 1817	G.L.O. Notes	Wampler	N/A	Post
N/A	Witnesses	N/A	N/A	3/4" Iron
1926	MDOT Road Plans	N/A	N/A	Ford Axle
1973	Survey L. 2364 P. 63	Patterson	#17631	N/A
1973	Survey L. 2380 P. 491	Patterson	#17631	N/A
1973	Survey L. 2364 P. 64	Patterson	#17631	N/A
1978	L.C.R.C. L. 2936 P. 228	Hooth	#7966	R.R. Spike
1987	MDOT Wit. Proj. #26271A	N/A	N/A	R.R. Spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10 I found an "X" cut in the left turn lane of northbound Van Dyke 30' West of the C/L of northbound Van Dyke Road (conc.) and on line of occupation running East (chain link fence). Measured East to found 1/2" rebar in conc monument (POB of Cert. Survey L. 2364, P. 64). Meas. = 659.93'; Record = 660.00'. No witnesses remain from above information.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/27/98

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Measure North 2676.38' to G-9 (G.L.O. = 2640.0') (1926 MDOT = 2678.0') (1978 MDOT = 2675.33')
 Measure South 2648.18' to G-11 (G.L.O. = 2640.0') (1926 MDOT = 2648.25') (1961 MDOT = 2649.77') (1987 MDOT = 2647.77')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 I set a 3/4" x 24" iron rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #25826." Also set a new monument box.


N 15° W 30.55'	Set Chiseled "X" on S Rim of Manhole
S 25° W 94.89'	Set Chiseled "X" on E Rim of Water Manhole
S 60° W 25.35'	Set P.K. Nail & Macomb Tag in S Side 6" Elm
S 45° E 82.60'	Set Chiseled "X" on N'ly Flange Bolt on Hyd. .35' Above Ground

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

Signed by Bruce Antcliff
 EARTH TECH

Date 11-25-98

Surveyor's Michigan License No. 25826



860